

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-22006-00-00  
Spot: N2N2NE Sec/Twnshp/Rge: 34-19S-10W  
330 feet from N Section Line, 1320 feet from E Section Line  
Lease Name: MCGUIRE Well #: 2  
County: RICE Total Vertical Depth: 3308 feet

Operator License No.: 3911  
Op Name: RAMA OPERATING CO., INC.  
Address: 101 S. MAIN  
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	3305	1700	125 SX CMT
SURF	10.75	210		165 SX CMT

**\$107.51**

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/29/2006 10:30 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Sand perfs to 2975' & cap w/ 7 sxs cmt. Cut off csg & pull to 1250' & pump 50 sxs cmt. Pull to 900' & pump 50 sxs cmt. Pull to 260' & circ cmt to surf.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL  
Date/Time Plugging Completed: 03/29/2006 1:30 PM KCC Agent: VIRGIL CLOTHIER

**Actual Plugging Report:**

Sanded perforations to 2900' and capped with 7 sacks of cement. Cut off 7" casing at 1700' and pulled out of hole. Ran tubing to 1250' and pumped 50 sacks of cement after pumped 1000 lbs of cotton hulls. Pulled tubing to 900' and pumped 50 sacks of cement. Pulled tubing to 260' and circulated cement to surface.

60/40 posmix with 4% gel

Allied #22564

**Perfs:**

Top	Bot	Thru	Comments
3214	3218		
3080	3086		
3028	3030		

**RECEIVED  
KCC DISTRICT #2  
APR 17 2006  
WICHITA, KS**

**RECEIVED  
MAY 01 2006  
KCC WICHITA**

Remarks:

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

**INVOICED**  
5-1-06  
2006061575 *ra*

*PKT*