

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-22011-00-00
Spot: E2SWSWNE Sec/Twnshp/Rge: 34-19S-10W
2970 feet from S Section Line, 2210 feet from E Section Line
Lease Name: MCGUIRE Well #: 3
County: RICE Total Vertical Depth: 3865 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S. MAIN
STAFFORD, KS 67578

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| PROD | 7 | 3620 | | |
| SURF | 10.75 | 207 | | |

\$125.00

Well Type: SWD UIC Docket No: D24277.0 Date/Time to Plug: 03/30/2006 2:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 03/30/2006 5:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

3/30/2006 -- Sanded perforations to 3380' an capped the 7 sacks of cement. Perforated at 1250', 900', and 260'. Ran tubing to 1250' and pumped 50 sacks of cement. Pulled tubing to 1050' and pumped gel and cotton hulls. Pulled tubing to 900' and pumped 50 sacks of cement with cotton hulls. Pulled tubing to 260' and attempted circulation to surface.

3/31/2006 -- Re-tagged cement top with tubing at 755'. Pumped 230 more sacks of cement to circulate cement to surface and circulated on backside of 7" casing.

60/40 posmix with 4% gel

Log Tech #4473

Allied #24161

Perfs:

RECEIVED
KCC DISTRICT #2
APR 17 2006
WICHITA, KS

Remarks:

Plugged through: TBG

RECEIVED
MAY 01 2006
KCC WICHITA

District: 02

INVOICED

Signed

Virgil Clothier
(TECHNICIAN)

DATE

5-1-06

TIME

20060615 7:57 AM

Form CP-2/3

PCT