

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-22426-00-00  
Spot: NWNWSESW Sec/Twnshp/Rge: 12-20S-10W  
1155 feet from S Section Line, 3795 feet from E Section Line  
Lease Name: HILL Well #: 1  
County: RICE Total Vertical Depth: 3337 feet

Operator License No.: 3911  
Op Name: RAMA OPERATING CO., INC.  
Address: 101 S. MAIN  
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2431		225 SX
SURF	8.625	240		165 SX

\$ 108.45

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/04/2006 1:30 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL  
Date/Time Plugging Completed: 04/04/2006 5:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 1320' and capped with 5 sacks of cement. Cement bond log of this well indicated cement top on backside at 1200'. Ran tubing to 1250' and pumped 45 sacks of cement with 100 lbs of cotton hulls to fill up to 900' where casing had been attempted to be cut off by Log Tech. Casing was re-cut at 716' and pulled to 290'. Cement was circulated to surface. Pulled casing out of hole and topped off.

60/40 posmix with 4% gel

Allied #24164

Perfs:

Top	Bot	Thru	Comments
2202	2206		
1430	1436		
1394	1410		

RECEIVED  
KCC DISTRICT #2  
APR 17 2006  
WICHITA, KS

RECEIVED  
MAY 01 2006  
KCC WICHITA

Remarks: PLUGGED THROUGH TUBING AND CASING.

Plugged through:

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

INVOICED  
DATE 5-1-06  
INVOICE NO. 2006061575

PLG