

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-20532-00-00  
Spot: SWNW Sec/Twnshp/Rge: 32-15S-8W  
3345 feet from S Section Line, 4732 feet from E Section Line  
Lease Name: HELWICK Well #: 3  
County: ELLSWORTH Total Vertical Depth: 2689 feet

Operator License No.: 5047  
Op Name: RUPE OIL COMPANY, INC.  
Address: 111 WHITTIER #1000 PO BOX 783010  
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2685		100 SX CMT
SURF	8.625	250		240 SX CMT

\$ 87.39

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/10/2006 1:30 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: FELIX TOBAR Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Sand perms to 2460', cap w/ 4 sxs cmt; 35 sxs @ 900', 35 sxs @ 600', circ to surf 300' - 0'.

Plugging Proposal Received By: GREG EVES Witness Type: PARTIAL  
Date/Time Plugging Completed: 04/10/2006 4:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

Sanded perforations to 2460' and capped with 4 sacks of cement. Pulled pipe to 900' and pumped 35 sacks of cement. Pulled pipe to 600' and pumped 35 sacks of cement. Pulled pipe to 300' and pumped 125 sacks of cement to circulate to surface.

1590' casing pulled  
195 sxs 60/40 posmix with 4% gel  
Allied #18483

Perfs:

Top	Bot	Thru	Comments
2673	2678		
2624	2638		
2509	2512		

RECEIVED  
KCC DISTRICT #2  
APR 18 2006  
WICHITA, KS

RECEIVED  
MAY 01 2006  
KCC WICHITA

Remarks:  
Plugged through: CSG

District: 02

Signed Greg Eves  
(TECHNICIAN)

INVOICED

5-1-06

2006061577

*a*

PKT