

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-01455-00-00  
Spot: NENESW Sec/Twnshp/Rge: 25-18S-8W  
2310 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: J R LANSING A Well #: 1  
County: RICE Total Vertical Depth: 3234 feet

Operator License No.: 9292  
Op Name: SCHECK, TIMOTHY DBA SCHECK OIL  
Address: 225 MAIN  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	3169		115 SX CMT
SURF	13	177		200 SX CMT

\$1 105.11

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/17/2006 1:30 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL  
Date/Time Plugging Completed: 03/17/2006 4:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 2700' and capped with 7 sacks of cement. Perforated at 1050', 700', and 250'. Ran tubing to 1050' and dumped 50 sacks of cement at 400 psi. Pulled tubing to 700' and pumped 50 sacks of cement at 100 psi. Pulled tubing to 250' and circulated cement to surface.

60/40 posmix with 4% gel

Log Tech #4461

Allied #23525

Perfs:

Top	Bot	Thru	Comments
2879	2881		
2847	2852		
2803	2808		

RECEIVED  
KCC DISTRICT #2  
APR 17 2006  
WICHITA, KS

RECEIVED  
MAY 01 2006  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed

Virgil Clothier  
(TECHNICIAN)

INVOICED

DATE 5-1-06  
2006061578  
SER. NO. \_\_\_\_\_

PKT