

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 130 SOUTH MARKET, SUITE 2078
 WICHITA, KANSAS 67202

API Well Number: 15-055-20023-00-00
 Spot: SESESW Sec/Twnshp/Rge: 8-22S-33W
333 feet from S Section Line, 3102 feet from E Section Line
 Lease Name: GARDEN CITY Well #: B-1
 County: FINNEY Total Vertical Depth: 4850 feet

Operator License No.: 30535
 Op Name: HARTMAN OIL CO., INC.
 Address: 12950 E. 13TH
WICHITA, KS 67230

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1790		WITH 2 SX CMT
CIBP		4100		WITH 2 SX CMT
DVT		2716		WITH 690 SX CMT
PROD	5.5	4949	0	WITH 280 SX CMT
SURF	8.625	393		WITH 250 SX CMT

\$ 157.63

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/13/2006 1:00 PM
 Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
 Proposal Rcvd. from: STAN MITCHELL Company: HARTMAN OIL Phone: (316) 636-2090

Proposed Plugging Method: RUN TUBING & PACKER TO 4000' +/- . PUMP HULLS & CMT TO PLUG OFF PERFS. SPOT CMT THROUGH TUBING & AT TOP OF PREMIAN. PERFORATE AT 900'. CIRCULATE CMT IN & OUT CASING VOLUME + 80 SX CMT. MAY HAVE TO PUMP DOWN BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
 Date/Time Plugging Completed: 04/14/2006 10:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

SET CIBP @ 4100' WITH 2 SX CMT. SET CIBP @ 1790' WITH 2 SX CMT. TESTED CASING TO 500# & HELD. PERFORATE AT 940'. PUMP 215 SX CMT DOWN 5 1/2" X 8 5/8" ANNULUS. FULL RETURNS OUT OF ANNULUS. CASING & ANNULUS STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4703	4710		
4619	4625		
4421	4427		
4276	4278		
4156	4170		

RECEIVED
 MAY 03 2006
 KCC WICHITA
 INVOICED
 DATE 5-4-06


Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

WT. NO. 2006061585

Plugged through: CSG

At

District: 01



Signed

Ken Jehlik

(TECHNICIAN)

PJT