

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-033-00100-00-01  
Spot: SWSE Sec/Twnshp/Rge: 24-34S-18W  
705 feet from S Section Line, 1950 feet from E Section Line  
Lease Name: MILLER Well #: 1 OWWO  
County: COMANCHE Total Vertical Depth: 5495 feet

Operator License No.: 6006  
Op Name: MOLZ OIL COMPANY  
Address: 19159 S.W. CLAIRMONT  
KIOWA, KS 67070

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5210		WITH 2 SX CMT
COND	16	161		WITH 250 SX CMT
PROD	5.5	5465	2400	WITH 150 SX CMT
SURF	9.625	874		WITH 1050 SX CMT

\$ 178,59

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/25/2006 10:45 AM  
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION  
Proposal Rcvd. from: BUD OSBORNE Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP 50' ABOVE PERFS & 2 SX CMT. PLUG AT 880' WITH 15 SX GEL & 60 SX CMT. PLUG AT 300' WITH 60 SX CMT. PLUG AT 40' WITH 30 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/25/2005 11:45 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5210' WITH 2 SX CMT. 1ST PLUG AT 880' WITH 15 SX GEL & 60 SX CMT. 2ND PLUG AT 315' WITH 60 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5273	5277		
5268	5277		
5262	5266		
5260	5268		

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: CSG

RECEIVED  
MAY 03 2006  
KCC WICHITA  
INVOICED  
DATE 5-4-06  
WEL. NO. 2006061586

District: 01

RECEIVED  
APR 28 2006  
KCC Dodge City

Signed Eric MacLaren  
(TECHNICIAN)

Form CP-2/3

PCT