

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-20323-00-00  
Spot: NWSWNW Sec/Twnshp/Rge: 12-10S-24W  
3630 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: GANO SE UNIT Well #: 1-4  
County: GRAHAM Total Vertical Depth: 4080 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4074	0	w/200 sxs cmt
SURF	8.625	187	0	w/150 sxs cmt

\$ 132.60

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/17/2006 9:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 567-8104

Proposed Plugging Method: Ordered 250 sxs Midcon II cement and 600# hulls.  
Plug through tubing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/17/2006 12:00 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 187' w/150 sxs cement.  
4 1/2" production casing set at 4074' w/200 sxs cement.  
PBTD 4055'. TD 4080'.  
Perforated 4 1/2" production casing at 2140' and 1275'.  
Ran tubing to 2281' - pumped 135 sxs cement and 500# hulls.  
Pulled tubing to 1074' - pumped 40 sxs cement and 75# hulls - cement to surface.  
Pulled tubing to surface. Connected to 4 1/2" production casing - pumped 20 sxs cement and 75# hulls.  
Max. P.S.I. 400#. S.I.P. 375#.  
Connected to 8 5/8" surface pipe - pumped 20 sxs cement.  
Max. P.S.I. 100#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
4034	4040		
4012	4016		
3976	3980		
3954	3958		
3902	3906		
3892	3898		
3864	3868		
3852	3856		
3820	3824		

RECEIVED  
MAY 03 2006  
KCC WICHITA

Remarks: LEASE ALSO KNOWN AS GENE GANO #4. SWIFT SERVICES, INC. #9906.

Plugged through: TBG

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

INVOICED

DATE 5-4-06  
INV. NO. 2006061588

Form CP-2/3

APR 18 2006

HPT

DGN E. PRATT  
HAYS, KANSAS

#4 GENE GANO

12-10-24W  
NW SW NW

CONTR L. J. DREILING & SONS.

CTY GRAHAM

GEOL

FIELD GANO SE

E 2479 KB CM 5/9/70 CARD ISSUED

7/16/70 IP P 65 BOPD + 20% WTR  
LKC 3892-96  
GR 42

API 15-065-20,323

LOG TOPS DEPTH DATUM

LOG	TOPS	DEPTH	DATUM
*ANHY		2097	+ 382
TOP		3564	-1085
HEEB		3781	-1302
TOR		3805	-1326
LKC		3921	-1342
BKC		4047	-1568
RTD		4080	-1601

8 5/8" 187/150sx; 4 1/2" 4074/200sx  
 DST(1) 3809-3882/2', 60'OCM, BHP 154-86#  
 IFP 43#, NO FFP  
 DST(2) 3878-3940/2', 300'GIP, 120'HM &  
 GCO, 120'SC & GCM, 120'SW, BHP 857-  
 849#, FP 43-206#  
 DST(3) 3924-4002/2', 180'M, 720'W, BHP  
 1417-1201#, FP 120-462#  
 MICT CC 4046 PF 3892-96, A350REG & SWB  
 DWN & SWB 1.68BOPH/2HRS + TR WTR SD/12  
 FU 500'OIL + 200'WTR SWB 1.68BOPH A1650  
 15% SWB LD & SHORT 18BF SWB 6.681ST HR  
 SWB 5.01 2ND HR, SWB 3.34 60-70%OIL  
 LAST 4HRS, POP

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

INDEX