

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 130 SOUTH MARKET, SUITE 2078
 WICHITA, KANSAS 67202

API Well Number: 15-081-20575-00-00
 Spot: NESESE Sec/Twnshp/Rge: 22-30S-34W
1014 feet from S Section Line, 544 feet from E Section Line
 Lease Name: MOSBARGER Well #: 3
 County: HASKELL Total Vertical Depth: 5800 feet

Operator License No.: 8767
 Op Name: TREES OIL COMPANY, THE
 Address: 3552 E. DOUGLAS
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2929		
PROD	4.5	3540	2216	WITH 375 SX CMT
SURF	8.625	1725		WITH 600 SX CMT

188.50

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/13/2006 8:00 AM
 Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
 Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 200# HULLS & 20 SX CMT. PLUG AT 1750' WITH 50 SX CMT. PLUG AT 650' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)
 Date/Time Plugging Completed: 04/14/2006 10:00 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PUMP 200# HULLS & 20 SX CMT. DISPLACE WITH MUD & PRESSURE TO 400#. 1ST PLUG AT 1750' WITH 50 SX CMT. 2ND PLUG AT 650' WITH 30 SX CMT. GOOD CIRCULATION. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2957	2963		
2932	2942		
2901	2914		
2890	2899		
2879	2887		

RECEIVED
 MAY 03 2006
 KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

District: 01

RECEIVED
 APR 25 2006
 KCC Dodge City

Signed Jim Holland PIRTELL
 (TECHNICIAN)

INVOICED
 DATE 5-4-06
 # 2006061591

[Handwritten signature]

RET