

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-23236-00-00

Spot: SENWNW

Sec/Twnshp/Rge: 33-14S-13W

4290 feet from S Section Line,

4290 feet from E Section Line

Lease Name: CARTER

Well #: 6

County: RUSSELL

Total Vertical Depth: 3249 feet

Operator License No.: 7281

Op Name: VONFELDT, ALAN J

Address: 128 EVES DRIVE
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3201	0	w/265 sxs cmt
SURF	8.625	671	0	w/300 sxs cmt

\$ 105.59

Well Type: SWD

UIC Docket No: D28260.0

Date/Time to Plug: 04/12/2006 10:30 AM

Plug Co. License No.: 31529

Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO

Company: VONFELDT, ALAN J.

Phone: (785) 483-6178

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 04/12/2006 1:00 PM

KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Sanded to 2840' and dumped 5 sxs cement.
Cut off casing at 1820'.
Pulled to 1275' - pumped 90 sxs 60/40 pozmix - 10% gel cement with 300# hulls.
Pulled to 725' - pumped 40 sxs cement with 100# hulls.
Pulled to 200' and circulated with 60 sxs cement.

RECEIVED
MAY 03 2006
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Case Morris

(TECHNICIAN)

INVOICED

DATE

5-4-06

FILE NO.

2006061592

APR 17 2006

Form CP-2/3

PKT

ALAN VONFELDT
RUSSELL KS 67665

33-14S-13W
SE NW NW

#6 CARTER

site 5-1/4 S & 3-3/4 W OF BUNKER HILL KS
contr: VONFELDT DRILLING #1
geol: DAVID M. SHUMAKER
fr date 09/05/2003
spc date 09/09/2003
drig comp 09/14/2003
card issued 11/10/2003
last revised 11/10/2003
APR 15-167-23236

8			

ELV: 1725 KB, 1720 GL SMP
tops.....depth/datum
ANH.....660 +1065
B/ANH.....696 +1029
GRDHAVEN.....2185 -460
TARK SD.....2201 -476
TARK SD-2.....2220 -495
TARK LM.....2254 -529
WILLARD.....2282 -557
ELMONT.....2321 -596
TOP.....2532 -807
HEEB.....2766 -1041
TOR.....2783 -1058
DOUG.....2799 -1074
LANS.....2830 -1105

IP status:

SWDW, ARB 3201-3211, 09/14/2003

BKC.....3095 -1370

ARB.....3123 -1398

LTD.....3211 -1486

RTD.....3211 -1486

NO LOG

CSG: 8-5/8" 671 / 300 SX (ALT 1), 5-1/2" 3201 / 265 SX

NO CORES OR DSTS

TRGT ZN: LKC, GORHAM (OIL), PTD 3200 (GORHAM), MICT

- CO, (ARB OH), AC 1000 GAL (28%), SWB LD, SET 2-1/2"

TBG & PKR AT 3195, COMP AS SWDW - INJECTION RATE

SATISFACTORY, 9/14/2003

COPYRIGHT 2003
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS