

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-20404-00-01
Spot: NWSE Sec/Twnshp/Rge: 3-33S-34W
1980 feet from S Section Line, 1980 feet from E Section Line
Lease Name: HITCH UNIT Well #: 1-1
County: SEWARD Total Vertical Depth: 6400 feet

Operator License No.: 4549
Op Name: ANADARKO PETROLEUM CORPORATI
Address: 1201 LAKE ROBBINS DRIVE
THE WOODLANDS, TX 77380

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		6000		WITH 2 SX CMT
PROD	5.5	6400	830	WITH 600 SX CMT
SURF	8.625	1640		WITH 750 SX CMT

\$ 206,000

Well Type: EOR UIC Docket No: E26115.1 Date/Time to Plug: 04/18/2006 10:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: CIBP @ 6050' WITH 2 SX CMT. PLUG AT 1670' WITH 50 SX CMT. PLUG AT 500' WITH 30 SX CMT. PLUG AT 40 WITH 10 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/19/2006 2:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

SET CIBP @ 6000' WITH 2 SX CMT. 1ST PLUG AT 1700' WITH 25 SX CMT INSIDE 5 1/2" CASING. 2ND PLUG AT 500' WITH 30 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6186	6196		
6130	6186		
6104	6130		


INVOICED
DATE 5-4-06
SER. NO. 2006061581

RECEIVED
MAY 03 2006
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

District: 01



Signed Jim Holland PIRT II
(TECHNICIAN)

Form 2573

PT