

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-20596-00-00  
Spot: NENENWSE Sec/Twnshp/Rge: 1-14S-21W  
2360 feet from S Section Line, 1630 feet from E Section Line  
Lease Name: LUEA Well #: 2  
County: TREGO Total Vertical Depth: 3922 feet

Operator License No.: 30717  
Op Name: DOWNING-NELSON OIL CO INC  
Address: PO BOX 372  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3920	0	75 SX CMT
SURF	8.625	284	0	180 SX CMT

\$ 127.47

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/20/2006 11:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: TERRY W PIESKER Company: DOWNING-NELSON OIL CO., INC. Phone: (785) 735-4363

Proposed  
Plugging  
Method:

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/20/2006 12:00 PM KCC Agent: ROGER MOSES

**Actual Plugging Report:**

Perforated at 1550' w/375 sxs. TOC at 1000'.  
Squeezed at 960' w/300 sxs (another squeeze - cement amount unknown).  
Swedge to 8 5/8" (4 1/2" casing cut off right below top of surface pipe).  
Squeezed 35 sxs cement, followed with 20 sxs gel and 40 sxs with 500# hulls.  
Max. P.S.I. 500#. S.I.P. 400#.  
Total of 75 sxs cement - 20 sxs gel and 500# hulls.

**Perfs:**

Top	Bot	Thru	Comments
3920	3922		

**INVOICED**  
DATE 5-4-06  
INV. NO. 2006061582  
**RECEIVED**  
MAY 03 2006  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. STEWART TANK. BLACKHAWK TANK-WATER.

Plugged through: CSG

District: 04

Signed

Roger L. Moses  
(TECHNICIAN)

APR 25 2006

ACT

HESS OIL CO.  
BOX 905

#2 LUEA

1-14-21W  
50'N & 350'E  
C N/2 NW SE

MC PHERSON, KS. 67460

CONTR MURFIN DRILLING

CTY TREGO

GEOL JERRY HOMAS

FIELD KROEGER SO EXT & CONC  
(1/8 S)

E 2247 KB CM 11/3/79 CARD ISSUED

1/24/80 IP

P 40 BQ & 20 BWPD  
ARB OH 3920-22

+	+	+
+	+	+
+	+	+

API 15-195-20,596

SMP	TOPS	DEPTH	DATUM
ANH	1577	+ 670	
B ANH	1622	+ 625	
TOP	3257	-1010	
HEEB	3509	-1262	
LANS	3550	-1303	
ARB	3519	-1672	
RTD	3922	-1675	

8-5/8" 284/180sx, 4 1/2" 3920/75sx

NO LOG

NO DST'S  
MICT - CO, (ARB OH), TST 1/4 BOPH, NAT,  
AC 250, SWB 11 BOPH, NW, 1100' OFF  
STM, POP

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

MAOICED