

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-21092-00-00
Spot: W2SWSESE Sec/Twnshp/Rge: 14-13S-21W
330 feet from S Section Line, 1090 feet from E Section Line
Lease Name: HALL Well #: 2
County: TREGO Total Vertical Depth: 3903 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 372
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3902	0	150 SX CMT
SURF	8.625	258	0	150 SX CMT

\$ 126.85

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/20/2006 9:15 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: TERRY W PIESKER Company: DOWNING-NELSON OIL CO., INC. Phone: (785) 735-4363

Proposed
Plugging
Method:

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/20/2006 10:30 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

Perforated at 1550' w/170 sxs (11/1982).
Tied to 5 1/2" casing - spotted 60 sxs cement with 300# hulls, followed with 23 sxs gel.
Squeezed 5 1/2" w/200 sxs cement and 200# hulls.
Max. P.S.I. 500#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3846	3852		
3699	3702		
3667	3680		
3657	3661		

RECEIVED
MAY 03 2006
KCC WICHITA

INVOICED

Remarks: BLACKHAWK TANK - STEWART TANK.

Plugged through: CSG

DATE 5-4-06
2006061582

District: 04

Signed

Roger L. Moses
(TECHNICIAN)


APR 25 2006

PACT

JOHN J. DARRAH, JR. #2 HALL 14-13-21W
 405 CENTURY PLAZA WICHITA, KS 67202-3296 330' FSL &
 CONTR MALLARD DRILG. CO., INC. CTY TREGO 1090' FEL, SE/4

GEOL _____ FIELD HOMBURG SO.

ELV 2218 KB SPD 10/11/82 CARD ISSUED 12/9/82 IP P 45 BOPD
 MARM 3846-3866 OA (NEW PAY)



API 15-195-21.092

LOG	Tops	Depth Datum
TOP		3253-1035
HEEB		3485-1267
TOR		3505-1287
LANS		3522-1304
BKC		3765-1547
MARM		3821-1603
ARB		3897-1679
PBTD		3885-1667
TD		3903-1685

8 5 8 " 258 150SX, 5 1 2 " 3902 150SX
 DST (1) 3543-3610 (LANS) 30-30-60-45, REC 110' M. 62' SL
 WM, SIP 641-435#, FP 103-133, 103-114#
 DST (2) 3761-3872 (MARM) 30-30-30-30, REC 920' FROGGY
 OIL, SIP 1081-1112#, FP 228-549#
 MICT - CO, PF (MARM) 3846-52 & 3857-66. W 2 SPF. AC
 1500G, SWB LD, R&T, POP, P 45 BOPD

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS