

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22253-00-00
Spot: S2SENE Sec/Twnshp/Rge: 20-13S-21W
2450 feet from N Section Line, 650 feet from E Section Line
Lease Name: DOUG EGGER Well #: 1-20
County: TREGO Total Vertical Depth: 4191 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 372
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
DVT		1674		180 SX CMT
PROD	5.5	4190	0	150 SX CMT
SURF	8.625	222	0	150 SX CMT

\$ 136.21

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/20/2006 8:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: TERRY W PIESKER Company: DOWNING-NELSON OIL CO., INC. Phone: (785) 735-4363

Proposed
Plugging
Method:

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/20/2006 9:00 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

DV tool at 1674' w/180 sxs cement - circulated.
Tied to 5 1/2" casing - spotted 60 sxs cement with 400# hulls, and 23 sxs gel.
Squeezed 5 1/2" casing w/170 sxs cement with 100# hulls.
Max. P.S.I. 500#. S.I.P. 300#.
Tied to 8 5/8" x 5 1/2" - pressured to 200# - took no cement.
Total of 230 sxs cement - 23sxs gel and 500# hulls.

Perfs:

Top	Bot	Thru	Comments
4070	4074		
4008	4014		
3730	3734		

RECEIVED
MAY 03 2006
KCC WICHITA

INVOICED

Remarks: STEWART TANK-BLACKHAWK TANK-WATER.

Plugged through: CSG

DATE 5-4-06
TIME 2006061582

District: 04

15

Signed

Roger A. Moses
(TECHNICIAN)

APR 25 2006

PET

DOWNING-NELSON OIL CO
HAYS KS 67601

20-13S-21W
2450' FNL & 650' FEL, SEC

#1-20 EGGER, DOUG

site 1-1/4 S & 5-1/2 W OF ELLIS KS
contr: DISCOVERY DRILLING #2
geol: RON NELSON

cy: TREGO
fiac: RIGA

API 15-195-22253

tr date 04/28/2004 spc date 05/06/2004 orig comp 05/13/2004 card issued 08/30/2004 last revised 08/30/2004

ELV: 2306 KB, 2298 GL LCG
tcpsdepth/datum
ANH1696 +610
E/ANH1740 +566
HEEB3621 -1315
LANS3657 -1351
EKC3932 -1626
MARM3992 -1686
CHER SH4037 -1731
CHER SD4067 -1761
CONG4084 -1778
RTD4191 -1885

IP status
OIL, P 40 BOPD, NW, MARM 3996-4014 OA, 05/25/2004
CSG: 8-5/8" 222.72 / 150 SX (ALT 2), 5-1/2" 4186.36 / 150 SX,
DV TOOL AT 1674 / 180 SX
COMMENT: MI & RURT 5/6/2004
NO CORES
DSTSTAKEN - DETAILS NA
TRGT ZN: LKC, ARB (OIL), FTD 4000 (ARB), MICT - CO, FF
(MARM) 3996-4000, 4007-4014, W / 4 SFF, AC 500 GAL
(MCA), SWB LD, GSO, SET 2-3/8" TEG AT 4150, NO FKR,
POP, IPP 40 EOPD, NW, NSG (GR 40), DOFP 5/25/2004 - NO
OTHER INFO AVAILABLE - TEMP COMP 8/30/2004

COPYRIGHT 2004
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS