

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-10045-00-00
Spot: SESESW Sec/Twnshp/Rge: 28-22S-33W
330 feet from S Section Line, 2340 feet from W Section Line
Lease Name: DAMME B Well #: 2
County: FINNEY Total Vertical Depth: 4894 feet

Operator License No.: 30535
Op Name: HARTMAN OIL CO., INC.
Address: 12950 E. 13TH
WICHITA, KS 67230

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 1175 | | |
| CIBP | | 4350 | | |
| PROD | 5.5 | 4894 | 0 | WITH 175 SX CMT |
| SURF | 8.625 | 375 | | WITH 175 SX CMT |

\$ 159.06

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/11/2006 1:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: STAN MITCHELL Company: HARTMAN OIL Phone: (316) 636-2090

Proposed Plugging Method: CIBP @ 4350. CIBP @ 1175'. TEST CIBP TO 500#. PERFORATE AT 1150'. MIX & PUMP CMT DOWN 5 1/2" CASING. MIX & PUMP CMT DOWN 8 5/8" x 5 1/2" ANNULUS.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/12/2006 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CASING LEAKS AT: 1182-1210' SQUEEZED W/75 SX CMT, 1190-1215' SQUEEZED W/75 SX CMT, 2722-23' SQUEEZED W/300 SX CMT, 3198' SQUEEZED W/150 SX CMT. SET CIBP @ 4350'. SET CIBP @ 1175'. TEST CASING TO 500# & HELD. PERFORATED AT 1150'. PUMPED 225 SX CMT DOWN 5 1/2" CASING. SHUT IN PRESSURE 500# & HELD. PUMPED 200 SX CMT DOWN 5 1/2" X 8 5/8" ANNULUS. SHUT IN PRESSURE 400# & HELD.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4780 | 4789 | | |
| 4710 | 4716 | | |
| 4456 | 4462 | | |
| 4412 | 4416 | | |
| 4380 | 4382 | | |

RECEIVED
MAY 03 2006
KCC WICHITA
INVOICED

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: CSG

DATE 5-4-06
TEL. NO. 2006061585

District: 01

RECEIVED
APR 20 2006
KCC Dodge City

Signed

Ken Jehlik
(TECHNICIAN)

[Signature]

PKT