

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-125-26789-00-00
Spot: SWNWNW Sec/Twnshp/Rge: 13-31S-15E
4200 feet from S Section Line, 5060 feet from E Section Line
Lease Name: GARNER A Well #: 2
County: MONTGOMERY Total Vertical Depth: 1160 feet

Operator License No.: 33074
Op Name: DART CHEROKEE BASIN OPERATING
Address: 600 DART RD PO BOX 177
MASON, MI 48854

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	1160	0	
SURF	8	40	0	

\$ 37.70

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/11/2005 8:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY
Proposal Rcvd. from: TONY WILLIAM Company: DART CHEROKEE BASIN OPERATI Phone: (620) 779-1028

Proposed Plugging Method: Plug well by connecting to wellhead and squeezing cement into well. When full of cement, shut the well in with pressure.

Plugging Proposal Received By: ALAN DUNNING Witness Type: NONE
Date/Time Plugging Completed: 11/11/2005 5:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

The well was hooked onto and filled with cement by squeezing. The well was shut in with 750 psi. Altogether, 42 sacks of portland cement were used to plug the well. The well was cut off below plow depth and the location restored.

Perfs:

RECEIVED
KCC DISTRICT #3

MAY 1 2006 AMD
CHANUTE, KS

DATE 5-9-06
2006061606

Remarks:

Plugged through: CSG

District: 03

Signed Alan M. Dunning
(TECHNICIAN)

RECEIVED
MAY 08 2006
KCC WICHITA

PWT