

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-043-20025-00-00  
Spot: SWNWSW Sec/Twnshp/Rge: 14-2S-20E  
1599 feet from S Section Line, 429 feet from W Section Line  
Lease Name: BUFFALO HOLLOW Well #: 1-14  
County: DONIPHAN Total Vertical Depth: 2166 feet

Operator License No.: 33233  
Op Name: HEARTLAND OIL & GAS, INC.  
Address: 1610 INDUSTRIAL PARK DRIVE  
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2141		
SURF	8.625	251		

# 70.40

Well Type: CM UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/23/2006 8:00 AM  
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.  
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: CEMENT FROM 2119' TO 2069', GEL FROM 2069' TO 300'. CEMENT FROM 300' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN Witness Type: NONE  
Date/Time Plugging Completed: 02/23/2006 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Tagged bottom at 2119'. Pumped 16.25 barrels of gel. Gel was placed from 2119' to 1669'. Pulled tubing to 1669' and pumped 19 barrels of gell and 15 sacks of cement with 1 sack of cotton seed hulls. The cement was placed from 1669' to 1473' and gel from 1473' to 300'. Pulled tubing to 283' and circulated 25 sacks of cement to surface.

Perfs:

RECEIVED  
KCC DISTRICT #3  
MAY 2 2006 TCH  
CHANUTE, KS

INVOICED  
DATE 5-9-06  
WEL. NO. 2006061610

Remarks:  
Plugged through: TBG

District: 03

Signed Taylor C. Herman  
(TECHNICIAN)

RECEIVED  
MAY 08 2006  
KCC WICHITA

PST