

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-22031-00-00  
Spot: SESESW Sec/Twnshp/Rge: 17-28S-9W  
330 feet from S Section Line, 2310 feet from W Section Line  
Lease Name: LEITER TC Well #: 1  
County: KINGMAN Total Vertical Depth: 4500 feet

Operator License No.: 9482

Op Name: NATIONAL PETROLEUM RESERVES, I

Address: 250 N. ROCK RD., STE 130  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	306		

Well Type: DH

UIC Docket No:

Date/Time to Plug: 04/23/2006 11:00 PM

Plug Co. License No.: 5142

Plug Co. Name: STERLING DRILLING COMPANY

Proposal Revd. from: LANNY SALOGA

Company: STERLING DRILLING COMPANY

Phone: (620) 672-9508

Proposed  
Plugging  
Method:

35 sxs @ 1500'; 35 sxs @ 700'; 35 sxs @ 350'; 25 sxs @ 60'; 15 sxs in rathole; and 10 sxs in mousehole.

Plugging Proposal Received By: STEVE VANGIESON

WitnessType: NONE

Date/Time Plugging Completed: 04/23/2006 1:15 PM

KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perfs:

The drill pipe was ran open end to 1500' where 35 sacks of cement was spotted. The drill pipe was pulled to 700' where 35 sacks of cement was spotted. The drill pipe was pulled to 350' where 35 sacks of cement was spotted. The drill pipe was pulled to 60' where 25 sacks of cement was circulated to surface. The rathole was circulated with 15 sacks of cement. The mousehole was circulated with 10 sacks of cement.

60/40 posmix with 4% gel

Acid Services #12505


RECEIVED  
KCC DISTRICT #2  
APR 24 2006  
WICHITA, KS

Remarks:

Plugged through: DP

District: 02

Signed



(TECHNICIAN)

INVOICED

DATE 5-5-06  
BY 2006061597

RECEIVED  
MAY 05 2006  
KCC WICHITA

Form CP-2/3

PKT