

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-22905-00-00
Spot: NW Sec/Twnshp/Rge: 34-16S-21W
3960 feet from S Section Line, 3960 feet from E Section Line
Lease Name: DAVIS Well #: 3-E
County: NESS Total Vertical Depth: 4200 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N. MARKET, STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1300		
DVT		1263		WITH 350 SX CMT \$ 136.50
PROD	5.5	4199	0	WITH 125 SX CMT
SURF	8.625	628		WITH 350 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/27/2006 10:20 AM
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: THAD Company: AMERICAN ENERGIES CORPORAT Phone: (316) 263-5785

Proposed Plugging Method: RUN TUBING TO PBSD. PUMP HULLS & 25 SX CMT. PULL TUBING TO 1100'. CIRCULATE CMT TO 0'. CHECK ANNULUS.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/27/2006 2:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TUBING TO 4095' & PUMP 25 SX CMT & 300# HULLS. SET CIBP @ 1300'. LOAD CASING AND PRESSURE TO 500#. RUN TUBING TO 1100' & PUMP 115 SX CMT. CIRCULATED TO SURFACE. PULLED TUBING AND TOPPED OFF WITH 10 SX CMT. TIED ONTO BACKSIDE AND PUMPED 10 SX CMT. PRESSURED TO 500# & HELD.

Perfs:


Top	Bot	Thru	Comments
4111	4114		

INVOICED
DATE 5-9-06
JOB NO. 2006061603

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: TBG

District: 01



Signed

Michael Maier

RECEIVED (TECHNICIAN)

MAY 08 2006

KCC WICHITA

Form NP-208

PCT