

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-22944-00-00
Spot: N2NWNWSW Sec/Twnshp/Rge: 34-16S-21W
2310 feet from S Section Line, 4780 feet from E Section Line
Lease Name: DAVIS E Well #: 4
County: NESS Total Vertical Depth: 4200 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N. MARKET, STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
DVT		1271		WITH 350 SX CMT
PROD	5.5	4196	0	WITH 450 SX CMT
SURF	8.625	635		WITH 325 SX CMT

\$ 136,50

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/19/2006 1:10 PM
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: THAD Company: AMERICAN ENERGIES CORPORAT Phone: (316) 263-5785

Proposed Plugging Method: PUMP 25 SX CMT & 300# HULLS. PUMP 22 SX GEL & 15 SX CMT. PRESSURE CHECK. PUMP 20 SX CMT DOWN BACKSIDE & PRESSURE TEST. TUN TUBING TO 1000' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/27/2006 11:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMP 25 SX CMT & 300# HULLS. PUMP 22 SX GEL THEN 15 SX CMT. PRESSURE TO 1800# AND SHUT OFF. TIED ONTO BACKSIDE & PUMPED 20 SX CMT. PRESSURED TO 500#. 4/27/06: DRILLED OUT CMT AND RAN TUBING TO 1000'. PUMPED 85 SX CMT & CIRCULATED CMT TO SURFACE. PULLED TUBING AND TOPPED OFF WITH 5 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4102	4105		

INVOICED
DATE: 5-9-06
2006061603

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: CSG

District: 01



Signed

Michael Maier
(TECHNICIAN)

RECEIVED
MAY 08 2006
KCC WICHITA

Form CR-23

PRT