

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-125-27032-00-01
Spot: NWNWNE Sec/Twnshp/Rge: 3-31S-15E
5115 feet from S Section Line, 1155 feet from E Section Line
Lease Name: LAVELY Well #: 4-C
County: MONTGOMERY Total Vertical Depth: 1586 feet

Operator License No.: 33074
Op Name: DART CHEROKEE BASIN OPERATING
Address: 600 DART RD PO BOX 177
MASON, MI 48854

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1586	0	
SURF	7	65	0	

\$ 51.55

Well Type: SWD UIC Docket No: D23422.0 Date/Time to Plug: 10/26/2005 8:00 AM
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC
Proposal Rcvd. from: TONY WILLIAMS Company: DART CHEROKEE BASIN OPERATI Phone: (620) 779-1028

Proposed Plugging Method: Run cement string to TD and fill from bottom to top with portland cement.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 10/26/2005 5:00 AM KCC Agent: ALAN DUNNING

Actual Plugging Report: Perfs:

The retrievable plug set at 1320 ft could not be removed. Therefore, a 2.375 inch cement string was run to 1315 ft. The well was filled from bottom to top thru the 2.375 inch cement string. Altogether, 125 sacks of 60/40 poz mix cement with 2% gel were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED
KCC DISTRICT #3
MAY 1 2006 AMD
CHANUTE, KS

INVOICED
DATE 5-9-06
2006061606

Remarks:
Plugged through: CSG

District: 03 Signed Alan Dunning
(TECHNICIAN)

RECEIVED
MAY 08 2006
KCC WICHITA

PICT