

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-043-20026-00-00
Spot: N2SESWNE Sec/Twnshp/Rge: 30-2S-20E
2270 feet from N Section Line, 1603 feet from E Section Line
Lease Name: RAWHIDE CAMP Well #: 1-30
County: DONIPHAN Total Vertical Depth: 1566 feet

Operator License No.: 33233
Op Name: HEARTLAND OIL & GAS, INC.
Address: 1610 INDUSTRIAL PARK DRIVE
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1550		236 SX CMT
SURF	8.625	263		22 SX CMT \$ 50.90

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/22/2006 8:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GEL FROM 1519' TO 1510', CEMENT FROM 1510' TO 1237', GEL FROM 1237' TO 300', CEMENT FROM 300' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: NONE
Date/Time Plugging Completed: 02/22/2006 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Tagged bottom at 1519'. Pumped 15 barrels of gel and 20 sacks of cement with 1 sack of cotton seed hulls. Cement was placed from 1519' to 1257' and gel from 1257' to 300'. Pulled tubing to 283' and circulated 25 sacks of cement to surface.

Perfs:

Top	Bot	Thru	Comments
1457	1460		
1369	1372		
1356	1359		
1341	1344		
1287	1290		

RECEIVED
KCC DISTRICT #3

MAY 2 2006 TCH

CHANUTE, KS

INVOICED
DATE 5-9-06
20060610

Remarks:

Plugged through: TBG

District: 03

Signed

Taylor C. Herman

(TECHNICIAN)

RECEIVED
MAY 08 2006
KCC WICHITA

Form CP-2/3

PLG