

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20069-00-01
Spot: SWNE Sec/Twnshp/Rge: 3-33S-41W
3300 feet from S Section Line, 1980 feet from E Section Line
Lease Name: BERRYMAN RICHFIELD UNIT Well #: 12-2W
County: MORTON Total Vertical Depth: 5100 feet

Operator License No.: 32659
Op Name: PHOENIX PETROCORP, INC.
Address: 15700 CUSTER TRAIL
FRISCO, TX 75035

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3180		WITH 2 SX CMT
PROD	4.5	5100	1500	
SURF	8.625	1510		

\$ 165.75

Well Type: EOR UIC Docket No: E18039.13 Date/Time to Plug: 04/25/2006 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DANNY BROSCOE Company: PHOENIX PETROCORP Phone: (972) 529-2544

Proposed Plugging Method: CIBP @ 3180' WITH 2 SX CMT. PLUG AT 1530' WITH 50 SX CMT. PLUG AT 720' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/26/2006 1:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

TUBING PARTED. TOP OF FISH @ 3180'. SET CIBP @ 3180' WITH 2 SX CMT. 1ST PLUG AT 1522' WITH 50 SX CMT. 2ND PLUG AT 750' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
5016	5034		

INVOICED
DATE 5-9-06
INV. NO. 2006061646

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: TBG

District: 01



Signed

Jim Holland PIRT#
(TECHNICIAN)

RECEIVED
MAY 08 2006
KCC WICHITA

Form CP-2/3

PKT