

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-013-20032-00-00
Spot: SWSE Sec/Twnshp/Rge: 34-1S-16E
660 feet from S Section Line, 2072 feet from E Section Line
Lease Name: RESCHKE Well #: 34-34
County: BROWN Total Vertical Depth: 2320 feet

Operator License No.: 33233
Op Name: HEARTLAND OIL & GAS, INC.
Address: 1610 INDUSTRIAL PARK DRIVE
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2298		491 SX CMT
SURF	8.625	60		20 SX CMT \$ 75.40

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/21/2006 8:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: CEMENT FROM 2250' TO 2200', GEL FROM 2200' TO 300',. CEMENT FROM 300' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: NONE
Date/Time Plugging Completed: 02/21/2006 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Tagged bottom at 2250'. Pumped 40.5 barrels of gel and 15 sacks of cement. Cement was placed from 2250' to 2119' and gel from 2119' to 300'. Pulled tubing to 283' and circulated 35 sacks of cement to surface.

Perfs:

RECEIVED
KCC DISTRICT #3
MAY 2 2006 TCH
CHANUTE, KS

INVOICED
DATE 5-9-06
TEL NO. 2006061610

Remarks:
Plugged through: TBG

District: 03

Signed Taylor C. Herman
(TECHNICIAN)

RECEIVED
MAY 08 2006
KCC WICHITA

PRT