

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-085-20060-00-00
Spot: NENE Sec/Twnshp/Rge: 30-6S-16E
810 feet from N Section Line, 525 feet from E Section Line
Lease Name: AMON Well #: 41-30 WD
County: JACKSON Total Vertical Depth: 3308 feet

Operator License No.: 33233
Op Name: HEARTLAND OIL & GAS, INC.
Address: 1610 INDUSTRIAL PARK DRIVE
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3302		725 SX CMT
SURF	8.625	217		102 SX CMT
T1	2.875	3247		

\$ 107.51

Well Type: SWD UIC Docket No: D28292.0 Date/Time to Plug: 02/14/2006 8:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: CEMENT FROM 3308' TO 3205', GEL FROM 3205' TO 250', CEMENT FROM 250' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN Witness Type: NONE
Date/Time Plugging Completed: 02/14/2006 5:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Tagged bottom at 3305'. Loaded hole with 65 barrels of gelled water and pumped 35 sacks of cement with 2 sacks of cotton seed hulls. Cement was placed at 3305' to 3001' and gel from 3001' to 250'. Pulled tubing to 278' and circulated 35 sacks of cement to surface.

Perfs:

Top	Bot	Thru	Comments
3255	3308		

RECEIVED
KCC DISTRICT #3
MAY 2 2006 TCH
CHANUTE, KS

INVOICED
DATE 5-9-06
INV. NO. 2006061610

Remarks:

Plugged through: TBG

District: 03

Signed Taylor C. Herman
(TECHNICIAN)

RECEIVED
MAY 08 2006
KCC WICHITA

PCT