

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-125-01222-00-00  
Spot: NWSEW Sec/Twnshp/Rge: 34-31S-15E  
1597 feet from N Section Line, 1654 feet from W Section Line  
Lease Name: LEYDA Well #: OW-1  
County: MONTGOMERY Total Vertical Depth: 850 feet

Operator License No.: 32654  
Op Name: JONES GAS CORPORATION  
Address: PO BOX 970  
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10	20		Btm of S/C is est.

\$ 35.00

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/29/2005 8:00 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY  
Proposal Rcvd. from: DON COLLINS Company: JONES GAS CORPORATION Phone: (620) 331-0477

Proposed Plugging Method: Put cement plugs at TD, 500 Ft, and 250 ft to surface

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE  
Date/Time Plugging Completed: 12/29/2005 5:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

Ran a 1 inch cement string to 850 ft with 1 sack of gel. Place a 50 ft plug of cement (20 sacks) at 850 ft. Ran 2 sacks of gel and pulled the 1 inch cement string to 500 ft and placed a 50 ft cement plug (20 sacks). Ran 1 sack of gel and pulled the 1 inch cement string to 250 ft and placed cement from 250 ft to surface. A total of 150 sacks of portland cement were used to plug well.

RECEIVED  
KCC DISTRICT #3  
MAY 4 2006 AMB  
CHANUTE, KS

RECEIVED  
MAY 11 2006  
KCC WICHITA

Remarks:

Plugged through: OH

District: 03

Signed

Alan M. Dunning  
(TECHNICIAN)

INVOICED  
DATE 5-11-06  
2006061629

PKT