

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-30155-00-00 ~~00~~ **02**
Spot: NENENW ^S Sec/Twnshp/Rge: 28-17S-8W
~~4950~~ ~~330~~ feet from ~~X~~ Section Line, 2970 feet from E Section Line
Lease Name: JOHNSON L OWWO Well #: 2-A
County: ELLSWORTH Total Vertical Depth: 3233 feet

KCC
PKT
5/11/06
Per
Walter m

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

PROD Size: 7 feet: 3212
SURF Size: 10.75 feet: 218

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/15/2004 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: Set CIBP above perms & put 7 sxs cement on top; perforate @ 1100', 800' & 280'; run tubing to 1100' & pump 50 sxs; pull tubing to 800' & pump 50 sxs; and pull tubing to 280' & circ to surf.
**RECEIVED
KCC DISTRICT #2
SEP 21 2004**

WICHITA, KS

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 09/15/2004 1:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

Set CIBP at 2810' and put 7 sacks of cement on top. Perforated at 1100', 800', and 280'. Ran tubing to 1100' and pumped 50 sacks of cement. Pulled tubing to 800' and pumped 50 sacks of cement. Pulled tubing to 280' and circulated cement to surface. Topped off with 4 yds of cement on 9/16/2004.

Loaded hole with 22 bbls water before pumping first cement salt plug.

Allied Cement #17699
Log Tech of KS #3880

60/40 posmix with 4% gel.

**RECEIVED
KANSAS CORPORATION COMMISSION
SEP 28 2004
CONSERVATION DIVISION
WICHITA, KS**

Remarks:

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

PKT