

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-19535-00-01 *KCC W HM*  
Spot: NWNENW Sec/Twnshp/Rge: 16-25S-5E  
4991 feet from S Section Line, 3759 feet from E Section Line  
Lease Name: ROBISON Well #: 3  
County: BUTLER Total Vertical Depth: 2493 feet

Operator License No.: 5420  
Op Name: WHITE & ELLIS DRILLING, INC.  
Address: PO BOX 48848  
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	15.5	140		UNKNOWN
PROD	4.5	2494		50 SX CMT <i># 81 02</i>
SURF	13	857		UNKNOWN

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/07/2005 8:00 AM  
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.  
Proposal Revd. from: DALLAS FLOWERS Company: FLOWERS PRODUCTION Phone: (316) 321-0550

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE  
Date/Time Plugging Completed: 10/07/2005 11:15 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

10/6/2005 -- Dumped 50 sacks of sand. Sanded back to 2430' and dump bailed 6 sacks of cement on top. Shot 4-1/2" casing at 288'. POOH with 288' of 4-1/2" casing. Pumped flag to check perforations of 13" casing. Flagged holes at 288'. Established circulation and pumped 347 sacks of 60/40 posmix with 4% gel to surface.

10/7/2005 -- Tagged cement at 105' and pumped 34 sacks of 60/40 posmix with 4% gel to surface. Cement to surface.

United #6542 and #6573

Perfs:

Top	Bot	Thru	Comments
2481	2483		

**RECEIVED  
KCC DISTRICT #2  
DEC 14 2005  
WICHITA, KS**

**RECEIVED  
JAN 03 2006  
KCC WICHITA**

Remarks:

Plugged through: TBG

District: 02

Signed

*Duane Krueger*

(TECHNICIAN)

**INVOICED**

DATE 1-3-06

INV. NO. 2006060938