

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-20706-00-00
Spot: SESWNE Sec/Twnshp/Rge: 24-1S-33W
2970 feet from S Section Line, 1650 feet from E Section Line
Lease Name: TIMM A Well #: 2
County: RAWLINS Total Vertical Depth: 4680 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 1321 W. 93 N.
VALLEY CENTER, KS 67147

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4411	0	575 SX CMT
SURF	8.625	344	0	250 SX CMT

\$ 152,110

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/24/2006 1:00 PM
Plug Co. License No.: 33645 Plug Co. Name: PLAINS, LLC
Proposal Rcvd. from: BILL SCHMIDT Company: DAYSTAR PETROLEUM, INC. Phone: (316) 772-0921

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 10% gel - 600# hulls.
Plug through casing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/24/2006 3:35 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 334' w/250 sxs cement.
4 1/2" production casing set at 4411' w/575 sxs cement.
PBSD 4366'. TD 4680'.
Production casing had holes.
Connected to 4 1/2" production casing - pumped 225 sxs cement with 550# hulls.
Max. P.S.I. 250#. S.I.P. 0#.
Connected to 8 5/8" surface pipe - pumped 10 sxs cement with 50# hulls.
Max. P.S.I. 250#. Casing head blew out. S.I.P. 0#.

Perfs:

Top	Bot	Thru	Comments
4183	4185		
4155	4158		
4137	4140		
4081	4085		
4059	4062		

RECEIVED
MAY 10 2006
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #24001.

Plugged through: CSG

District: 04

Signed Darrel Dipman

(TECHNICIAN) BOB

INVOICED
DATE May 10, 2006
TEL. NO. 2006061622

Form CP-2/3

MAY 02 2006

PKT

