

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-21865-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 32-15S-21W
1650 feet from S Section Line, 4950 feet from E Section Line
Lease Name: HALBLEIB B Well #: 1
County: TREGO Total Vertical Depth: 4415 feet

Operator License No.: 6569
Op Name: SCHMITT, CARMEN, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4414	0	150 SX
SURF	8.625	232	0	150 SX

\$ 143.49

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/02/2006 9:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: JACOB PORTER Company: SCHMITT, CARMEN INC. Phone: (620) 793-2540

Proposed Plugging Method: Ordered out 355 sxs 60/40 pozmix - 10% gel - 500# hulls.
DV Tool at 1787' - cemented to surface.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/02/2006 11:30 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Swaged onto 5 1/2" - mixed and pumped 300 sxs cement with 500# hulls.
Max. P.S.I. 1000#. S.I.P. 300#.
Hooked up to the annulus - instant 400#.

Perfs:

Top	Bot	Thru	Comments
4293	4298		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

INVOICED
5-12-06
2006061639

Signed

Jay Pfeifer

(TECHNICIAN)

BOB

RECEIVED

MAY 12 2006

KCC WICHITA

Form CP-2/3

MAY 09 2006

PT

REPLACEMENT CARD
32-15-21W
SW NW SW

C & C EXPLORATION, INC.
14 CIRCLE DRIVE
BELOIT, KS. 67420

CONTR #1 HALBLEIB-B


GEOL RICHARD O'DONNELL

CTY TREGO

FIELD KUTINA SO. EXT
(1/8 E)

ELV 2393 KB SPD 8/4/86 CARD ISSUED 2/5/87 W P 56 BOPD, NW
2385 GL DRLG COMP 8/12/86 W CHER 4293-4298

API 15-195-21,865



LOG	Top	Depth/Datum
SC		1708 + 685
HEEB		3745-1352
TOR		3768-1375
LANS		3785-1392
STARK		4000-1607
BKC		4054-1661
PAW		4138-1745
LABETTE		4202-1809
FT SC		4212-1819
CHER SH		4236-1843
CHER B SD		4267-1874
BASAL PENN		4292-1899
MISS		4318-1925
PBTD		4299-1906
RTD		4415-2022

8 5/8 " 232 / 150 SX, 5 1/2 " 1845 / 150 SX
NO CORES
DST (1) 4001-4018 (LKC) / 45-45-45-45, 180' GIP, REC 15' OIL, 345' W, SIP 1264-1225#, FP 29-108 / 137-177#, HP 1945-1945#
DST (2) 4291-4308 (CHER) / 10-30-5-0, REC 5' OIL SPKD M, ISIP 729#, FP 29-29 / 29-29#, HP 2259-2168#
DST (3) 4297-4323 (MISS) / MISRUN
DST (4) 4290-4323 (MISS) / 10-30-10-30, REC 15' M, SIP 739-719#, FP 49-49 / 59-59#, HP 2259-2228#
MICT - CO, PF (CHER) 4293-4298, W / 2 SPF, AC 500 GAL (15% FEA), SLI SO, FRAC 10,000# SD & GEL (AMT NA), GSO, SET 2 7/8 - TBG AT 4192, POP, P 56 BOPD, NW, 8/30/86

INFO RELEASED: 3/19/87 - WAS OIL WELL - TIGHT HOLE

COPYRIGHT 1987
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS