

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21567-00-00
Spot: SESENW Sec/Twnshp/Rge: 20-7S-17W
2310 feet from N Section Line, 2310 feet from W Section Line
Lease Name: ELDON KRILEY F Well #: 2
County: ROOKS Total Vertical Depth: 3293 feet

Operator License No.: 5663
Op Name: HESS OIL COMPANY
Address: PO BOX 1009
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3284	0	150+ 180 AT SURFACE
SURF	8.625	1140	0	400 SX

\$ 107.02

Well Type: OIL UIC Docket No: 56603 Date/Time to Plug: 04/27/2006 2:30 PM
Plug Co. License No.: 32028 Plug Co. Name: CHITO'S WELL SERVICE, L.L.C. Hess oil co. KCC PKT 5/10/06
Proposal Rcvd. from: ARNIE HESS Company: HESS OIL COMPANY Phone: (785) 731-2869
per operator

Proposed Plugging Method: Ordered out 425 sxs 60/40 pomix - 10% gel - 600# hulls.
High fluid level. Perforate 1120' - two holes.
Ran tubing to plug.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/27/2006 5:15 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

LK Wireline perforated two holes at 1120'.
Ran tubing to 1800' - pumped 200 sxs neat followed with 100 sxs cement with 600# hulls mixed in.
Pulled tubing to 1200' - rigged to tubing and pumped 75 sxs to circulate cement to surface.
Pulled tubing - rigged to 5 1/2" casing with a swedge and pumped 15 sxs cement.
Max. P.S.I. 500#. S.I.P. 450#.
Rigged to 8 5/8" - pressured to Max. P.S.I. 2000#. S.I.P. 2000#.

Perfs:

Top	Bot	Thru	Comments
3282	3292		OPEN HOLE
3134	3135		
3085			
3046	3050		
2988	2990		

RECEIVED
MAY 10 2006
KCC WICHITA

Remarks: GRESSEL OIL FIELD SERVICES. PAT STAAB WITNESSED 50% WITH RICHARD WILLIAMS.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

BOB

INVOICED
DATE 5-10-06
2006061624

Form CP-2/3

MAY 08 2006

PKT

