

TO:  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING  
 130 SOUTH MARKET, SUITE 2078  
 WICHITA, KANSAS 67202

KCC PKT 5/10/06  
 Per ACO-1 + CP-1  
 MW

API Well Number: 15-163-21216-00-00

Spot: S2N2NW

Sec/Twnshp/Rge: 29-7S-17W

990 feet from N Section Line,

660 feet from W Section Line

Lease Name: KRILEY A

Well #: 1

County: ROOKS

Total Vertical Depth: 3298 feet

Operator License No.: 5663

Op Name: HESS OIL COMPANY

Address: PO BOX 1009  
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3297	0	200 SX
SURF	8.625	1150	0	250 SX

\$ 107.19

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 04/26/2006 12:00 PM

Plug Co. License No.: 5663

Plug Co. Name: HESS OIL COMPANY

Proposal Rcvd. from: ARNIE HESS

Company: HESS OIL COMPANY

Phone: (785) 731-2869

Proposed Plugging Method: Ordered out 385 sxs 60/40 pozmix - 10% gel - 600# hulls.  
 Well flowing water out 4 1/2" casing and 8 5/8".  
 Retrievable bridge plug and packer stuck at 2630' with seven joints tubing on top.  
 Emergency plug orders - flowing well.  
 Perforate 4 1/2" at 1125' - two holes.

Plugging Proposal Received By: RICHARD WILLIAMS

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 04/26/2006 3:30 PM

KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2590'. Allied pumped 275 sxs 60/40 pozmix - 10% gel neat.  
 Circulated cement out of 8 5/8" and 4 1/2" casing.  
 PTOH. Squeezed with 100 sxs cement and 600# hulls.  
 Max. P.S.I. 500#. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3297	3303		OPEN HOLE
3280	3290		
3256	3272		
3162	3164		
3135	3141		
3124	3126		
3050	3054		

RECEIVED  
 MAY 10 2006  
 KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams

BOB

(TECHNICIAN)

INVOICED

DATE 5-10-06  
2006061624

MAY 08 2006

PET

29-7-17W  
 G S/2 N/2 NW

COLUMBIA PETROLEUM INCORPORATED #1 KRILEY  
 PARKADE PLAZA CTY ROOKS  
 COLUMBIA, MO. 65201 LAWBANCO DRILLING FIELD RIFFE  
 CONTR ERIC WADDELL P 80 BOPD & TR W  
 GEOL CARD ISSUED 5/28/81 IP ARB 3280-90

+	+	+
+	+	+
+	+	+

E 1782 KB CM 1/8/81  
 1777 GL 15-163-21,216

LOG	TOPS	DEPTH	DATUM
ANH	1188	± 594	
TOP	2708	- 926	
HEEB	2920	-1138	
TOR	2944	-1162	
LKC	2962	-1180	
B KC	3190	-1408	
ARB	3242	-1460	
LTD	3278	-1496	
RTD	3298	-1516	
DDTD	3303	-1521	

8-5/8" 1150/250sx, 4 1/2" 3297  
 NO DST'S  
 MICT - CO, PF (ARB) 48/3256-72, AC  
 250 G, FU 30' OPH, THRU CSG, AC 1000  
 G (15% NE), FU 65' OPH, NW, AC 2000  
 G (28%) & 150# SALT PLUG, FU 800' O,  
 NW, 800' FROM SURF, SWB 30 BOPH, COULD  
 NOT LOWER FLUID, POP, P ALL WTR, OFF  
 PMP, SQZ'D 3256-72 W/CMT, DD 3303 TD,  
 ONFU 1250' O, NW, NAT EVERY HR, SET BP  
 @ 3290, PF (ARB) 3280-90, AC 250 G  
 (15%), FU 1000' OPH, PULL PLUG, SWB  
 DOWN, FL 10% WTR (SHOW OIL IN MARM 3200-  
 BOPD & 10% WTR (SHOW OIL IN MARM 3200-  
 10, LKC 'K' 3161-63; LKC 'J' 3136-42,  
 (OVER)

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS