

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22521-00-00
Spot: NESESW Sec/Twnshp/Rge: 2-16S-14W
990 feet from S Section Line, 2970 feet from E Section Line
Lease Name: BATT Well #: 3
County: BARTON Total Vertical Depth: 3390 feet

Operator License No.: 9292
Op Name: SCHECK, TIMOTHY DBA SCHECK OIL
Address: 225 MAIN
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3389	0	w/unknown sxs cmt
SURF	8.625	261	0	w/175 sxs cmt

\$ 110.18

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/21/2006 8:30 AM
Plug Co. License No.: 9292 Plug Co. Name: SCHECK, TIMOTHY DBA SCHECK OIL OPERATION
Proposal Rcvd. from: TIM SCHECK Company: SCHECK, TIMOTHY DBA SCHECK Phone: (785) 483-3404

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/21/2006 9:30 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Tied onto backside and pressured up - blew out slips.
Tied onto casing and pumped 245 sxs 60/40 pozmix - 10% gel cement with 600# hulls.
Max. P.S.I. 500#. S.I.P. 200#.

RECEIVED
MAY 10 2006
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Case Morris

(TECHNICIAN)

BOB

INVOICED

5-10-06

2006066626

MAY 04 2006

PKT

ENERGY THREE, INC.

P. O. BOX 1505

#3 BATT

2-16-14W
NE SE SW

GREAT BEND, KS 67531

CONTR BIG THREE

BARTON

GEOL BRAD HUTCHISON

FIELD TRAPP

E 1875 KB CM 12/22/81 ^{CARD} ISSUED 2/25/82

IP P 40 BOPD, NW

+	+
+	+

API 15-009-22,521

ARB 3309-3320 OA

SMP	TOPS	DEPTH	DATUM
ANH	858	+1018	
TOP	2792	- 916	
HEEB	3018	-1142	
TOR	3035	-1159	
BR LM	3086	-1210	
LKC	3102	-1226	
ARB	3304	-1428	
RTD	3390	-1514	

8-5/8" 261/175sx, 4 1/2" 3389

DST (1) 3295-3310/45-45-45-45, 145'
HO&GCM, (15% G, 45% M, 5% W, 35% O)
SIP 887-852#, FP 35-40/56-70#

DST (2) 3315-3330/45-45-45-45, 45'
HO&GCM & 45' OCM, SIP 1002-946#,
FP 49-61/61-68#

MICT - CO, PF (ARB), 3317-3320 & 3309-
3312, AC 3750G (20%) POP, P 40 BOPD,
NW, 1/28/82

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS