

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-24270-00-00

Spot: SESESW

Sec/Twnshp/Rge: 13-13S-19W

330 feet from S Section Line,

2970 feet from E Section Line

Lease Name: DREILING A

Well #: 1

County: ELLIS

Total Vertical Depth: 3720 feet

Operator License No.: 6246

Op Name: BENNETT & SCHULTE OIL CO., A GEN

Address: 140 WEST WICHITA AVE.
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3718	0	w/150 sxs cmt
SURF	8.625	217	0	w/140 sxs cmt

\$ 120.90

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 04/25/2006 11:30 AM

Plug Co. License No.: 31172

Plug Co. Name: L & M WELL SERVICING, INC.

Proposal Rcvd. from: ARNOLD MICHAELIS

Company: BENNETT & SCHULTE OIL CO.

Phone: (785) 483-2721

Proposed
Plugging
Method:

Ordered out 250 sxs 60/40 pozmix - 10% gel - 19 sxs gel - 500# hulls.
Well perf at 1300' and circulated with 400 sxs cement.

Plugging Proposal Received By: HERB DEINES

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 04/25/2006 3:30 PM

KCC Agent: JAY PFEIFER

Actual Plugging Report:

TIH with tubing to 3503' - mixed and pumped 50 sxs cement with 400# hulls.
Pulled up to 3100' - spotted 19 sxs gel.
Pulled up to 1400' - circulated cement with 90 sxs cement and 100# hulls.
POOH. Swaged onto 5 1/2" - topped with 70 sxs cement.
S.I.P. 500#.
Annulus full or cement - instant 500#.

Perfs:

Top	Bot	Thru	Comments
3668	3678		
3534	3538		
3439	3442		
3276	3278		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Jay Pfeifer

BOB

(TECHNICIAN)

INVOICED

5-12-06

DATE

2006061636

TIME

RECEIVED

MAY 12 2006


KCC WICHITA

Form CP-2/3

MAY 09 2006

PGT

T.J.D. OIL COMPANY
 BOX 127 #1 'A' DREILING 13-13-19W
 HAYS, KS. 67601 SE SE SW
 CONTR DREILING OIL, INC. CTY ELLIS
 GEOL LARRY GRAY FIELD GATSCHET
 ELV 2055 KB SPD 7/24/85 CARD ISSUED 9/26/85 IP P 22.5 BOPD & TR
 2050 GL DRLG COMP 8/1/85 WTR
 ARB 3668-3678



SMP	Tops	Depth/Datum	API 15-051-24,270
ANH		1338 + 717	8 5/8 " 217 / 140SX, 5 1/2 " 3716 / 150SX
TOP		3076-1021	DST (1) 3318-50 (SHAW) / 30-30-30-30, REC 5' M, SIP 206-
HEEB		3319-1264	98#, FP 13-13 / 14-14#
TOR		3336-1281	DST (2) 3368-3415 (LKC) / 30-30-30-30, REC 10' M, SIP 296-
LKC		3362-1307	96#, FP 13-13 / 14-14#
BKC		3593-1538	DST (3) 3668-83 (ARB) / 30-45-30-45, REC 588' CL OIL, SIP
ARB		3663-1608	1057-1038#, FP 29-89 / 98-167#
RTD		3720-1665	MICT - CO, PF (ARB) 3668-78, AC 250G (15% MA), SWB DWN, GSO, SQZ'D BACKSIDE (TWO-STAGED) W/450SX, POP, P 22.5 BOPD & TR WTR (GR 27"), 8/28/85