

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-24822-00-00
Spot: S2S2SE Sec/Twnshp/Rge: 3-13S-16W
330 feet from S Section Line, 1320 feet from E Section Line
Lease Name: OTTILIA Well #: 5
County: ELLIS Total Vertical Depth: 3465 feet

Operator License No.: 5252
Op Name: NIXON, R P OPERATIONS, INC
Address: 207 W 12TH
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3460	0	w/125 sxs cmt
SURF	8.625	210	0	w/140 sxs cmt

112.61

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/25/2006 9:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: DUANE ACTERBERY Company: NIXON, R.P. OPERATIONS, INC. Phone: (785) 628-3834

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 10% gel - 500# hulls.
Well perforated at 1113' and circulated cement with 300 sxs.
Squeezed at 2110' - 2190' w/20 sxs.

Plugging Proposal Received By: JAY PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/25/2006 11:30 AM KCC Agent: JAY PFEIFER

Actual Plugging Report: _____ Perfs: _____

TIH with tubing to 2010' - mixed and circulated cement with 180 sxs cement with 350# hulls.
POOH. Swaged onto 4 1/2" and topped with 45 sxs cement.
S.I.P. 300#.
Annulus full of cement - Instant 800#.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

INVOICED
5-12-06
2006070637

Signed

Jay Pfeifer

BOB

(TECHNICIAN)

RECEIVED

MAY 12 2006

KCC WICHITA

Form CP-2/3

MAY 09 2006

P&T

STATE: KANSAS COUNTY: ELLIS 3-13S-16W
FIELD: EMMERAM S2 S2 SE
OPER: NIXON R P OPERATIONS 330 FSL 1320 FEL SEC
WELL: 5 OTTILIA WELL CLASS: DO ELEV: 1979 GR
API: 15-051-24822 STATUS: OIL
SPUD: 12/07/92 COMP: 04/11/93
DTD: 3465 LTD: FTD: ARBUCKLE PBTD: 3376

LOC: 1/2 MI SE EMMERAM, KS

IP: COMP 4/11/93, OIL WELL PROD ZONE- TORONTO 3170-3172
NO CORES OR DSTS FILED CONFIDENTIAL W/STATE

LOG TOPS:

ANHYDRITE	1102 877	LANSING-KANSAS CITY	3202 -1223
TOPEKA	2937 -958	B/ LANSING-KANSAS CITY	3442 -1463
HEEBNER	3151 -1172	ARBUCKLE	3460 -1481
TORONTO	3170 -1191		
TD	3465 -1486		

LOG TYPES: GR;

CSGS: 8 5/8 @ 210 W/140 SX, 4 1/2 @ 3460 CMT; RIG REL 12/13/92
PERFS: PERF (LANSING-KANSAS CITY) 3362-3364 W/2 PF, PERF (LANSING-KANSAS CITY)
3274-3274 W/2 PF, ACID W/500 GALS, ,

(OVER)

COPYRIGHT 1993 PETROLEUM INFORMATION CORPORATION

DATE 06/11/93 CARD # 00005-KS