

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-62-3-117

API NUMBER 15-175-00046-00-01

LEASE NAME Angell A

WELL NUMBER 1-3

1980 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 3 TWP. 32S RGE. 33W (E) or (W)

COUNTY Seward

Date Well Completed 10/13/61

Plugging Commenced 01/15/04

Plugging Completed 01/15/04

RECEIVED
JAN 23 2004
KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Chesapeake Operating, Inc.

ADDRESS P. O. Box 18496, Oklahoma City, OK 73154-0496

PHONE# (409) 848-8000 OPERATORS LICENSE NO. 32334

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 06/25/03 (date)

by David Williams (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Chester Depth to Top 5313 Bottom 5315 T.D. 6493'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Surf</u>			<u>1779</u>	<u>8-5/8</u>	<u>1779'</u>	<u>0</u>
<u>Prod</u>			<u>5951</u>	<u>4-1/2"</u>	<u>5951'</u>	<u>0</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. MIRU Allied Cmt Co., pump down 4-1/2" csg w/250# hulls, follow w/20 sx cmt w/50# hulls, plug down, followed by 90 bbls mud for displacement, max PST 750#, MIRU Log-Tech, perf @1780', pump 460 sx cmt circ to surface, max PST 650#, IS, RDMO Allied & Log Tech, Used 480 sx 60/40 6% gel & 300# hulls. P&A'd 01/15/04

Name of Plugging Contractor Allied Cementing Co., Inc. License No. 99996

Address P. O. Box 31, Russell, KS 67665 (785)483-2626

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Chesapeake Operating, Inc.

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Jim Reisch (Employee of Operator) or (Operator) of above-described well, being first sworn on oath, says: That I have knowledge of the facts statements, and matters here contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) _____

(Address) P.O. Box 18496, Okla. City, OK 73154-0496

SUBSCRIBED AND SWORN TO before me this 21st day of January, 2004

My Commission Expires: April 17, 2007

Jamie R. Brody
Notary Public



Form CP-1
Revised 05-88

Jan-23-04 10:48A

P.04

ALLIED CEMENTING CO., INC. 13783

Federal Tax I.D. #

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: OAKLEY

DATE <u>1-14-04</u>	SEC. <u>3</u>	TWP. <u>925</u>	RANGE <u>33W</u>	CALLED OUT	ON LOCATION <u>11:45 AM</u>	JOB START <u>12:00 PM</u>	JOB FINISH <u>1:45 PM</u>
WELL # <u>ANGEL "A"</u>	WELL # <u>1-3</u>	LOCATION <u>Sublette 7S-2W-5S-N2W10</u>			COUNTY <u>Seward</u>	STATE <u>Ks</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)							

CONTRACTOR NONE OWNER SAME

TYPE OF JOB Old Hole

HOLE SIZE _____ T.D. _____

CASING SIZE 4 1/2" DEPTH _____

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

CEMENT	AMOUNT ORDERED	PRICE	TOTAL
300# HULLS	450 SKS	60/100 = .60	27000
COMMON	270 SKS	@ 8.35	2254.50
POZ MIX	180 SKS	@ 3.80	684.00
GEL	23 SKS	@ 10.00	230.00
CHLORIDE		@	
HULLS 300#		@ 18.00	5400.00
HANDLING 450 SKS		@ 1.15	517.50
MILEAGE 054 MI @ 5K/MI			675.00
TOTAL			4415.00

EQUIPMENT

PUMP TRUCK CEMENTER TERRY

300 HELPER WAYNE MAX

BULK TRUCK DRIVER JIM

357

BULK TRUCK DRIVER _____

REMARKS:

MIX 250# HULLS 205 SKS CEMENT NOT #
50# HULLS + DISPLACE 90 BBLs MUD.
PERF AT 1730' MIX 430 SKS CEMENT
CEMENT DED CIRC.

SERVICE

DEPTH OF JOB _____

PUMP TRUCK CHARGE _____ 225.00

EXTRA FOOTAGE @ _____

MILEAGE 30 MI @ 12.50 _____

PLUG @ _____

TOTAL 225.00

CHARGE TO: CHESAPEAKE OPERATIONAL

STREET _____

CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

TOTAL _____

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE Dennis Paul

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Dennis Frick

PRINTED NAME _____

RECEIVED
 KANSAS CORPORATION COMMISSION
 JAN 23 2004