

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
MAY 08 2006
KCC WICHITA
Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Hess Oil Company
Address: P. O. Box 1009
Phone: (620) 241-4640 Operator License #: 5663
Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: _____ (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Kans. City Depth to Top: 3050' Bottom: 3141' T.D. _____
Arbuckle Depth to Top: 3280' Bottom: 3303' T.D. 3303'
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 163-21,216-00-00
Lease Name: Kriley "A"
Well Number: 1
Spot Location (QQQQ): _____ - S2 - NW - NW
990 Feet from North / South Section Line
660 Feet from East / West Section Line
Sec. 29 Twp. 7 S. R. 17 East West
County: Rooks
Date Well Completed: 1/14/81
Plugging Commenced: 4/26/06
Plugging Completed: 4/26/06

Show depth and thickness of all water, oil and gas formations.


Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		1182'	0'	8-5/8"	1182' 1150	none KCC Pkt
		3297'	0'	4-1/2"	3297'	none 5/9/06
						Per CP2/3

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Tubing stuck in hole @ 2638'. Perf. @ 1125', ran tubing to 2590', circulated 275 sacks cement around 4-1/2" casing annulus and inside 4-1/2" casing, pulled tubing, and pumped in 100 sacks cement plus 600# hulls down 4-1/2" casing. Used 60/40 pozmix, 10% gel.

Name of Plugging Contractor: Hess Oil Company License #: 5663
Address: same
Name of Party Responsible for Plugging Fees: Hess Oil Company
State of Kansas County, McPherson, ss.
Bryan Hess, President

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Bryan Hess
(Address) same

SUBSCRIBED and SWORN TO before me this 4th day of May, 20 06

Carol A. Nickel
Notary Public My Commission Expires: 6-1-09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Pkt

ALLIED CEMENTING CO., INC. 25825

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Russell

DATE <u>4-26-06</u>	SEC. <u>29</u>	TWP. <u>7</u>	RANGE <u>17</u>	CALLED OUT <u>10:45 AM</u>	ON LOCATION <u>12:15 PM</u>	JOB START <u>12:45 PM</u>	JOB FINISH <u>3:30 PM</u>
LEASE <u>Kriely</u>		WELL # <u>A#1</u>		LOCATION <u>Stackton 1S 1 1/2 E</u>		COUNTY <u>Rooks</u>	STATE <u>KANSAS</u>
<input checked="" type="radio"/> OLD OR NEW (Circle one)				<u>1/4 S 1/4 E 1/4 N INTO</u>			

CONTRACTOR Express Well Service
 TYPE OF JOB Plug ABANDONED well
 HOLE SIZE _____ T.D. _____
 CASING SIZE 4 1/2 DEPTH 3297
 TUBING SIZE 2" DEPTH 2590'
 DRILL PIPE 8 5/8 SURFACE DEPTH 1150
 TOOL _____ DEPTH _____
 PRES. MAX 500# MINIMUM 300#
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. 2638' FISH
 PERFS L-K 1125
 DISPLACEMENT _____

OWNER _____
 CEMENT (Used 375 SK)
 AMOUNT ORDERED 385 SK 60 1/40 10% Gre

EQUIPMENT

PUMP TRUCK # <u>398</u>	CEMENTER <u>GREN</u>
BULK TRUCK # <u>396</u>	HELPER <u>GARY</u>
BULK TRUCK # _____	DRIVER <u>Kyle</u>
BULK TRUCK # _____	DRIVER _____

600# Hulls

COMMON _____	<u>225 @ 9⁰⁰</u>	<u>2160⁰⁰</u>
POZMIX _____	<u>150 @ 5²⁰</u>	<u>780⁰⁰</u>
GEL _____	<u>26 @ 15⁰⁰</u>	<u>390⁰⁰</u>
CHLORIDE _____	@ _____	_____
ASC _____	@ _____	_____
<u>HULLS</u>	<u>6 @ 23⁰⁰</u>	<u>138⁰⁰</u>

RECEIVED
 MAY 08 2006
 KCC WICHITA

HANDLING _____	<u>417 @ 1²⁰</u>	<u>708⁰⁰</u>
MILEAGE <u>65 Ton Mile</u>	@ _____	<u>1897³⁵</u>
TOTAL		<u>6674²⁵</u>

REMARKS:

Ran 2" Tubing to 2590' Mixed 275 SK Cement, Cement Circulated Around ANNULAS, and inside 4 1/2 CSG. Pulled Tubing, Hooked up to 4 1/2 CSG & Squeezed in ANOTHER 100 SK Cement w/ 600# Hulls @ 500# max Shot in @ 300#.

(Signature)

CHARGE TO: Hess Oil Company
 STREET _____
 CITY _____ STATE _____ ZIP _____

SERVICE

DEPTH OF JOB _____	PUMP TRUCK CHARGE _____	<u>650⁰⁰</u>
EXTRA FOOTAGE _____	MILEAGE <u>65</u>	@ <u>5⁰⁰</u> <u>325⁰⁰</u>
MANIFOLD _____	@ _____	_____
_____	@ _____	_____
_____	@ _____	_____

TOTAL 975⁰⁰

PLUG & FLOAT EQUIPMENT

_____	@ _____	_____
_____	@ _____	_____
_____	@ _____	_____
_____	@ _____	_____