

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Phoenix PetroCorp, Inc

Address: 15700 Custer Trail, Frisco, TX 75035

Phone: (972) 529-2544 Operator License #: 32659

Type of Well: WIW Docket #: E-18,039
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: or about 4/26/06 (Date)

by: Jim Holland (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Morrow Depth to Top: 5016' Bottom: 5034' T.D. 5100'
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-129-20069-00-01/9/06

Lease Name: Berryman Richfield unit

Well Number: 12-2w

Spot Location (QQQQ): _____ - C - SW - NE
3500 3300

Feet from North / South Section Line

1980 Feet from East / West Section Line

Sec. 3 Twp. 33 S. R. 41 East West

County: Morton

Date Well Completed: 10/22/71

Plugging Commenced: 4/26/06

Plugging Completed: 4/26/06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Morrow	Oil	0	1510'	8 5/8"	1510'	0
		0	5100'	4 1/2"	5100'	1512'
		0	4964'	2 3/8"	4964'	3584'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set 4 1/2" CIBP @ 3180' w/2 sx cement on top, cut csg collar @ 1512, lay down 1512' of 4 1/2" csg; fill with drilling mud to surface; set 50 sx.

cement plug @ 1522' w/60-40 POZ Cement; set 50 sx. cement plug @ 750' w/60-40 POZ Cement;

cement from 60' to surface w/ 60-40 POZ Cement.

Name of Plugging Contractor: Allied Cement Co. License #: 32659


Address: 15700 Custer Trail, Frisco, TX 75035

Name of Party Responsible for Plugging Fees: Phoenix PetroCorp, Inc

State of Texas County, Collin, ss.

James H. Williams (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) James H Williams

(Address) 15700 Custer Trail, Frisco, Tx 75035

SUBSCRIBED and SWORN TO before me this 3rd day of May, 2006

Cindy J. Tarbox My Commission Expires: March 30, 2008
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
MAY 04 2006
KCC WICHITA

KCC stat 06 PKT
per CP 2/3
99996

PKT