

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

RECEIVED  
MAY 08 2006  
Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
blanks must be Filled  
KCC WICHITA

Lease Operator: Oxy USA, Inc.  
Address: PO Box 2528 Liberal KS 67905  
Phone: (620) 629-4200 Operator License #: 5447  
Type of Well: Gas Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 4-11-06 (Date)  
by: Jim Holland (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Chase Depth to Top: 2652 Bottom: 2751 T.D. 4670  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-189-22161-00-02  
Lease Name: Taylor C  
Well Number: 2  
Spot Location (QQQQ): \_\_\_\_\_ - NW - SW - SE  
490 Feet from  North /  South Section Line  
2280 Feet from  East /  West Section Line  
Sec. 23 Twp. 34 S. R. 35  East  West  
County: Stevens  
Date Well Completed: 4-30-97 Spud  
Plugging Commenced: 4-11-06  
Plugging Completed: 4-11-06

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	1516	-
				5 1/2	6627	-

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mixed 400 lb. hulls & 25 sx cement to plug perfs from 2652 to 2452, mud spacer to 1550, mixed 25 sx 1550 to 1350, mud to 500, mixed 60 sx 500 to 0. Mixed 5 sx down annulus from 30 to 0. Cut off 8 5/8 & 5 1/2 & capped 8 5/8 6 ft. below G.L.

Name of Plugging Contractor: SARGENT AND HORTON PLUGGING, INC. License #: 31151  
Address: Rt. 1, Box 49 BA Tyrone, OK 73951-9731  
Name of Party Responsible for Plugging Fees: Oxy USA Inc. 1701 N. Kansas PO Box 2528 Liberal, KS. 67905  
State of Kansas County, Seward, ss.


Kenny Andrews (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Kenny Andrews

(Address) PO Box 2528 Liberal, KS 67905

SUBSCRIBED and SWORN TO before me this 3<sup>rd</sup> day of May, 2006

Anita Peterson My Commission Expires: Oct. 1, 2009  
Notary Public



Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PGT