

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
**This Form must be Typed**  
Form must be Signed  
All blanks must be Filled

API # 15 - 185-22910 0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date \_\_\_\_\_.

Well Operator: KENNETH S. WHITE KCC License #: 30128  
(Owner / Company Name) (Operator's)  
Address: 2400 N. Woodlawn, Suite 115 City: Wichita  
State: KS Zip Code: 67220 Contact Phone: ( 316 ) 682 - 6300  
Lease: Nelson Well #: 1 Sec. 32 Twp. 25 S. R. 11  East  West  
SW - NE - NE - Spot Location / QQQQ County: Stafford

990 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)  
4290 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: 10-3/4 Set at: 256 Cemented with: 175 Sacks  
Surface Casing Size: 8-5/8 Set at: 916 Cemented with: 200 Sacks  
Production Casing Size: 5-1/2 Set at: 4188 Cemented with: 100 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perfs @ 3943' to 3972'

Elevation: 1840 ( G.L. /  K.B.) T.D.: 4230 P.B.T.D.: 4146 Anhydrite Depth: 1130' - 1760'  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Fill with sand to 3900' and dump 5 sx cement, shoot casing for recovery, pull casing and plug @ 650' w/50 sx cement, 70 sx @ 250', 15 sx @ 40', 60/40 PozMix, 6% gel

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? Sent in when drilled

**RECEIVED**  
**MAR 02 2006**  
**KCC WICHITA**

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: \_\_\_\_\_

Herb Durant Phone: ( 620 ) 886 - 5463

Address: P.O. Box 251 City / State: Medicine Lodge KS 67104

Plugging Contractor: Mike's Testing & Salvage, Inc. KCC License #: 31529

Address: P.O. Box 467, Chase KS 67524 Phone: ( 620 ) 938 - 2943  
(Company Name) (Contractor's)

Proposed Date and Hour of Plugging (if known?): 3/14/06 - 3:00PM

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 3/1/2006 Authorized Operator / Agent: Kenneth S. White  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*\* well already plugged - dg*

*DST 01*