

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION**
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
**This Form must be Typed
Form must be Signed
All blanks must be Filled**

API # 15 - 151-22137-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date _____.

Well Operator: KENNETH S. WHITE KCC License #: 30128
(Owner / Company Name) (Operator's)
Address: 2400 N. Woodlawn, Suite 115 City: Wichita
State: Kansas Zip Code: 67220 Contact Phone: (316) 682 - 6300
Lease: Zink Well #: 1 Sec. 4 Twp. 26 S. R. 11 East West
NW - SE - SE - _____ Spot Location / QQQQ County: Pratt

990 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)
990 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 10-3/4" Set at: 255 Cemented with: 225 Sacks
Production Casing Size: 5-1/2" Set at: 4166 Cemented with: 175 Sacks

List (ALL) Perforations and Bridgeplug Sets: 4010-4030', 4032', 4034', 4036', 4038-4044', all one shot per foot

Elevation: 1840 (G.L. / K.B.) T.D.: 4170 P.BTD: 4145 Anhydrite Depth: 1110' - 1780'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Fill with sand to 3900' and dump 5 sacks cement, shoot casing for recovery, pull casing and plug @ 650' w/50 sx cement, 70 sx @ 250', 15 sx @ 40', 60/40 PozMix, 6% gel

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No
If not explain why? Sent in when well drilled

RECEIVED
MAR 02 2006
KCC WICHITA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: _____
Herb Durant Phone: (620) 886 - 5463

Address: P.O. Box 251 City / State: Medicine Lodge KS 67104

Plugging Contractor: Mike's Testing & Salvage, Inc. KCC License #: 31529
(Company Name) (Contractor's)
Address: P.O. Box 467, Chase KS 67524 Phone: (620) 938 - 2943

Proposed Date and Hour of Plugging (if known?): 3/9/06 - 2:30 PM

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent
Date: 3/1/2006 Authorized Operator / Agent: Kenneth S. White
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

** Well already plugged - Dlg.*

Dst 01