

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING APPLICATION**  
*Please TYPE Form and File ONE Copy*

Form CP-1  
September 2003  
**This Form must be Typed  
Form must be Signed  
All blanks must be Filled**

API # 15 - 151-22159-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date \_\_\_\_\_.

Well Operator: KENNETH S. WHITE KCC License #: 30128  
(Owner / Company Name) (Operator's)

Address: 2400 N. Woodlawn, Suite 115 City: Wichita

State: Kansas Zip Code: 67220 Contact Phone: ( 316 ) 682 - 6300

Lease: Green Well #: 1 Sec. 33 Twp. 26 S. R. 12  East  West

E/2 - NE - NW Spot Location / QQQQ County: Pratt

660 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

2310 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well

SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: None Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 10-3/4" Set at: 316 Cemented with: 250 Sacks

Production Casing Size: 5-1/2" Set at: 4429 Cemented with: 135 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perf @ 4332-35, CIBP @ 4330, Perf @ 4317-20, CIBP @ 4302, Perf @ 4283-88,

CIBP @ 4280, Perf @ 4222-26

Elevation: 1907 ( G.L. /  K.B.) T.D.: 4429 P.B.T.D.: 4280 Anhydrite Depth: 1260' - 1920'  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Fill with sand to 4150' and dump 5 sx cement, shoot casing for recovery, pull casing and plug @ 1920' with 50 sx cement, 75 sx cement @330', 25 sx @ 40', 60/40 PozMix, 6% gel

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? Filed with ACO-1

**RECEIVED  
MAR 02 2006  
KCC WICHITA**

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: \_\_\_\_\_

Herb Durant Phone: ( 620 ) 886 - 5463

Address: P.O. Box 251 City / State: Medicine Lodge, KS 67104

Plugging Contractor: Mike's Testing & Salvage, Inc. KCC License #: 31529  
(Company Name) (Contractor's)

Address: P.O. Box 467, Chase KS 67524 Phone: ( 620 ) 938 - 2943

Proposed Date and Hour of Plugging (if known?): 3/17/06 - 2:00 pm

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 3/1/2006 Authorized Operator / Agent: Kenneth S. White  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*\* Well already plugged - Dig -*

*Dist 01*