

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

RECEIVED  
MAR 02 2006  
KCC WICHITA

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-191-22394-000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR A G V Corp. KCC LICENSE # 5039  
(owner/company name) (operator's)

ADDRESS 123 N Main CITY Attica

STATE Ks ZIP CODE 67009 CONTACT PHONE # ( 620-254-7222

LEASE Haskins WELL# A1 SEC. 26 T. 32 R. 4 (East West)

SW - NE SPOT LOCATION/0000 COUNTY Sumner

3557 1830 FEET (in exact footage) FROM (N) (circle one) LINE OF SECTION (NOT Lease Line)  
*GPS & KCC app*

2079 1980 FEET (in exact footage) FROM (E/W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL \_\_\_ GAS WELL X D&A \_\_\_ SWD/ENHR WELL \_\_\_ DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE None SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 267' CEMENTED WITH 175 SACKS

PRODUCTION CASING SIZE 5 1/2 SET AT 3083 CEMENTED WITH 150.. SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3001-3006

ELEVATION 1219 T.D. 3087 PBDT 3083 ANHYDRITE DEPTH \_\_\_\_\_  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD X POOR \_\_\_ CASING LEAK \_\_\_ JUNK IN HOLE \_\_\_

PROPOSED METHOD OF PLUGGING Set cast iron bridge plug at 2950' cap with 2 SX cement, cut and pull pipe to 650', spot 35 sx cement, pull pipe to 320' circulate cement to surface  
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Larry G. Mans PHONE# 620-254-7222

ADDRESS 123 N Main City/State Attica, Ks 67009

PLUGGING CONTRACTOR Basye Well Service Inc. KCC LICENSE # 33204  
(company name) (contractor's)

ADDRESS 517 S Main Stafford, ks 67578 PHONE # (620) 234-5235

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 3/1/2006 - 2:00 pm

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 2/28/2006 AUTHORIZED OPERATOR/AGENT: Larry G. Mans  
(signature)

\* Well plugged - rec. Dig