

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - NA 195-00700-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 12/4/56.

Well Operator: VESS OIL CORPORATION (Owner / Company Name) KCC License #: 5030 (Operator's)

Address: 8100 E. 22nd Street North, Bldg. 300 City: Wichita

State: KS Zip Code: 67226 Contact Phone: (316) 682-1537 X101

Lease: Spaulding B Well #: #3 Sec. 1 Twp. 11S S. R. 21W East West

- NW - NE - NE Spot Location / QQQQ County: Ellis

4950' Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

990' Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8" Set at: 183' Cemented with: 175 Sacks

Production Casing Size: 5-1/2" Set at: 3650' Cemented with: 100 Sacks

List (ALL) Perforations and Bridgeplug Sets: 3112-42'; 3544-50'; 3634-37'; CIBP - 3645'; 3650-82' (OH)

Elevation: 2077' (G.L. / K.B.) T.D.: 3682' P.B.T.D.: 3645' Anhydrite Depth: 1528'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): In accordance with KCC rules and regulations

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? NA

RECEIVED
MAY 08 2006
KCC WICHITA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Joel Stull

Phone: (785) 483-9169

Address: P.O. Box 307 City / State: Natoma, KS 67651

Plugging Contractor: Allied Cementing Co., Inc. KCC License #: 99996
(Company Name) (Contractor's)

Address: P.O. Box 31, Russell, KS 67665-0031 Phone: (785) 483-2627

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 5/5/06 Authorized Operator / Agent: [Signature]
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

IMPERIAL OIL ANSAS, INC.
Well Completion Report

Spaulding Lease. Well No. "B" 3
 Loc. NW NE NE Sec. 1 Twp. 11S Rge. 21W
 County Trego State Kansas
 Pool Spaulding

Spud Date 12-4-56
 Rotary Completed 12-13-56
 Completion Date 12-17-56
 Potential 276 BOPD
 Gravity 31.6
 R. T. D. 3650
 Cable Tool TD 3657

Surface casing set at (8 5/8) 183 with 175 sacks
 Production casing set at (5 1/2) 3650 with 100 Sacks

Formation Tops:
 Elevation: 2077 KB

	Sample	Electric Log	Produced To
Anhydrite	1528 (4549) 2077		Jan. 1957 750
Heebner	3313 (-1226) 2087		Jan. 1958
Toronto	3335 (-1248) 2087		Jan. 1959
Lansing	3351 (-1274) 2077		Jan. 1960
Arbuckle	3646 (-1569) 2077		Jan. 1961
			Jan. 1962
			Jan. 1963
			Jan. 1964
			Jan. 1965
			Jan. 1966
			Jan. 1967

PRODUCING AND PROSPECTIVE PRODUCING ZONES

Formation	Depth	Feet	Remarks	Estimated Reserves
Lansing 200' Z	3540-49	9	DST Rec. 60' HOCM	
Simpson 3629-34 & 3636-39		8		
Arbuckle	3646-57	43	Decapped 3682 Open hole	105,000

No other zones worthy of testing.

RECEIVED
MAY 04 2006
KCC WICHITA

Completion Data: 12-14-56

Moved in; rigged up. Drilled staging collar. Swabbed hole dry.

12-15-56

Drilled shoe @ 3650. Drilled 2' formation 3650-52. Bailer test showed 16 gal. OPH. Drilled from 3652-56. 4 hr. swab test showed 2 BOPH. Drilled from 3655-57. 12 hr. swab test showed 9 BOPH off bottom.

12-16-56

Treated with 1000 gal. reg. acid using permeter to protect shoe. Highest pressure used 1000#. Pressure dropped to 400# in 5 min.

12-17-56

10 hr. swab test showed 12 BOPH off bottom no water. Ran tubing and rods; tore down, moved out.

3-19-57

Moved in; rigged up. Pulled tubing and rods. Swabbed hole down. 3 hr. swab test off bottom 12 BOPH.

3-20-57

Started drilling, drilled from 3657-69. 8 hr. swab test showed well making 28 BOPH after deepening.

3-21-57

Ran tubing using Chemical Process permeter set at 3660. Treated from 3660-69 with 2000 gal. re acid. Highest pressure 1250#. Pressure dropped to 250# in 2 min, to 0# in 3 min. Pulled tubing and started swab test.

3-22-57

11 hr. swab test 18 BOPH 900' off bottom. Drill from 3669-82. 5 hr. swab test 900' off bottom 22 BOPH.



KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Vess Oil Corporation
8100 E. 22nd N. Bldg. 300
Wichita, KS 67226

May 09, 2006

Re: SPAULDING B #3
API 15-195-00700-00-00
NWNENE 1-11S-21W, 330 FNL 990 FEL
TREGO COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #4
2301 E. 13th
Hays, KS 67601
(785) 625-0550

Sincerely



David P. Williams
Production Supervisor