

RECEIVED
KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
 September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

MAY 05 2006

KCC WICHITA

API # 15 - 113207380000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date _____.

Well Operator: White Hawk Oil Company KCC License #: 05163
(Owner / Company Name) (Operator's)

Address: P.O. Box 3363 City: Tulsa

State: Oklahoma Zip Code: 74101 Contact Phone: (918) 582 - 1022

Lease: A. Crowther Well #: 3 Sec. 27 Twp. 17 S. R. 1 East West

near C - SW - NE - XX Spot Location / QQQQ County: McPherson

Dlg KCC 2080 3199 6 P5-8. Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)
2080 2091 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # 19880 ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 216' Cemented with: 75 Sacks

Production Casing Size: 5 1/2" Set at: 3448' Cemented with: 200 Sacks

List (ALL) Perforations and Bridgeplug Sets: None

Elevation: 1395 (G.L. / K.B.) T.D.: 3735' P.B.T.D.: _____ Anhydrite Depth: 190' to 220'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Could not get below 370' after working on well for 5 days. Run 2 1/2" tubing in 370' and circulate cement to surface up 5 1/2" and 8 5/8".

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No Filed C-10 7/15/80

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: _____

Bruce Dirks Phone: (620) 654 - 8449 (cell)

Address: 372 340th City / State: Tampa/Kansas 67483

Plugging Contractor: United Cementing & Acid Co., Inc. KCC License #: n/a
(Company Name) (Contractor's)

Address: 2510 W. 6th St., Eldorado, KS 67042 Phone: (316) 321 - 4680

Proposed Date and Hour of Plugging (if known?): April 27, 2006

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 5/1/06 Authorized Operator / Agent: Mandi Taylor
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

** Already plugged - Dlg*

Dist 02



Blackstone Drilling, Inc.

Box 1184 • 523 West Kansas • Phone (316) 241-1250
McPHERSON, KANSAS 67460

June 23, 1980

RECEIVED
MAY 05 2006
KCC WICHITA

COMPANY: WHITE HAWK OIL COMPANY
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: A. CROWTHER SWD #3
 COMMENCED: June 9, 1980
 COMPLETED: June 22, 1980
 LOCATION: 560' EWL & 560' NSL NE/4 Section 27-17-1W,
 McPherson County, Kansas
 ELEVATION: '

0	to	70	Clay
70	to	190	Shale
190	to	220	Anhydrite
220	to	610	Lime & Shale
610	to	1062	Shale & Lime
1062	to	1393	Shale
1393	to	1668	Lime & Shale
1668	to	2180	Shale & Lime
2180	to	2360	Lime & Shale
2360	to	2742	Lime
2742	to	2770	Mississippi
2770	to	2959	Lime
2959	to	3074	Shale
3074	to	3090	Hunton
3090	to	3251	Lime
3251	to	3332	Lime & Shale
3332	to	3380	Shale
3380	to	3735	Arbuckle
		3735	T. D.

Cut 12 1/2" hole to 216' and run 216' of 8 5/8" hole with 75 sacks of cement. Plug down at Noon, 12:00, June 10, 1980. Run 3448' of 5 1/2" casing, cemented with 200 sacks of cement at 3448. Plug hole at 4:00 P. M., June 22, 1980.

TOPS: M MISSISSIPPI - 2742' HUNTON - 3074' ARBUCKLE - 3380'


Measurements taken from K. B.

CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of your log on your A. Crowther SWD #3 located on the 560' EWL & 560' NSL NE/4 Section 27-17-1W, McPherson County, Kansas as reflected by the files of Blackstone Drilling, Inc.


 P. E. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 23rd day of June, 1980.


 Johnnie L. Schmidt - Notary Public

