

KANSAS

Form CP-3
Rev. 6-26-62

RP

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-20163-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Leo J. Dreiling Oil Company,

Complete Address: Victoria, Kansas. R. R. #2

Lease Name Hale Well No. 1

Location CNW-NE Sec. 10 Twp. 7 Rge. (E) (W) 23

County Graham Total Depth 3887

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: L. J. Dreiling & Sons, Incorporated,

Address: Victoria, Kansas. License No.

Operation Completed: Hour 9:00 PM Day 12 Month 8 Year 1968

The Above well was plugged as follows:

174'--8 5/8" Surface pipe, cement circulated with 150 Sx.
Top of Dakota section @ 985'.

Circulated hole with heavy mud. Pulled DP to 1210' and displaced 100 Sx. cement thru
DP from 1210' to 885'. Pulled DP to 210' and displaced 20 Sx. cement thru DP from
210' to 150'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

CONSERVATION DIVISION
Wichita, Kansas

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 8/14/68
INV. NO. 8276-u

8-14-68