

15-065-20197-00-00

Form CP-3  
Rev. 6-26-62



KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 27 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
JAN 27 1969

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Chief Drilling Company, Incorporated,

Complete Address: Box #797, Great Bend, Kansas.

Lease Name Davis Well No. 1

Location S/2-NE-SE Sec. 31 Twp. 7 Rge. (E) (W) 25

County Graham Total Depth 3910

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Above

Address:      License No.     

Operation Completed: Hour 12:00M Day 21 Month 1 Year 1969

The Above well was plugged as follows:

203'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 975'.

Circulated hole with heavy mud. Pulled DP to 1200' and displaced 100 Sx. cement thru  
DP from 1200' to 875'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from 215'  
to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of  
cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. S. Dickel  
Well Plugging Supervisor

INVOICED  
DATE 1/27/69  
INV. NO. 9243-W