



KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 6 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
OCT 6 1970

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Murfin, Kantor and Executive,

Complete Address 617 Union Center Building, Wichita, Kansas,

Lease Name Hurlbut Well No. 1

Location NW-SE-NE Sec. 31 Twp. 7 Rge. (E) (W) 25

County Graham Total Depth 3960'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center Building, Wichita, Kansas, License No.       

Operation Completed: Hour 7:00 PM Day 2 Month 10 Year 1970

The above well was plugged as follows:

287'---8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 1000'.

Circulated hole with heavy mud. Pulled DP to 1225' and displaced 100 Sx. cement thru  
DP from 1225' to 900'. Pulled DP to 320' and displaced 25 Sx. cement thru DP from  
320' to 245'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols  
Well Plugging Supervisor

DATE 10-6-70

INV. NO. 2637-W