

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
JAN 23 1967
JAN 23, 1967

Operator's Full Name John O. Farmer, Incorporated,

Complete Address: 370 W. Wichita, Russell, Kansas.

Lease Name Heskett Well No. 1

Location NE-NE-SW Sec. 32 Twp. 7 Rge. (E) (W) 25

County Graham Total Depth 3967

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 4:30PM Day 18 Month 1 Year 1967

The Above well was plugged as follows:

207'--8 5/8" Surface pipe, cement circulated with 135 Sx.

Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx.

cement thru DP. Heavy mud to 210', set plug with 1/2 sack hulls and dis-

placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack

hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/23/67
INV. NO. 4642-4

Signed: N. L. Nichols
Well Plugging Supervisor