



KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 16 1968
CONSERVATION DIVISION
Wichita, Kansas
Dec 16, 1968

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Three "G" Oil, Incorporated,

Complete Address: 1101 Wichita Plaza Building, Wichita, Kansas.

Lease Name Woodside Well No. 1

Location SW-NE-NE Sec. 34 Twp. 7 Rge. (E) (W) 25

County Graham Total Depth 2561

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Dunne-Gardner Drilling Company, Incorporated,

Address: 300 Schweiter Building, Wichita, Kansas. License No.

Operation Completed: Hour 3:30 AM Day 12 Month 12 Year 1968

The Above well was plugged as follows:

240'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1000'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 100 Sx. cement thru
DP from 1250' to 925'. Pulled DP to 240' and displaced 25 Sx. cement thru DP from 240'
to 165'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. L. Dehals
Well Plugging Supervisor

DATE 12/17/68
INV. NO. 9047-W